


Feb. 17, 1978 - Approval given to Credit Corp
to re-enter this old well.

9-5-78 - Completed as shut-in gas well

FILE NOTATIONS	
Entered in NID File	<input checked="" type="checkbox"/>
Entered On S R Sheet	<input type="checkbox"/>
Location Map Pinned	<input checked="" type="checkbox"/>
Card Indexed	<input checked="" type="checkbox"/>
IWR for State or Fee Land	<input type="checkbox"/>
Checked by Chief	<u>RJD</u>
Copy NID to Field Office	<input checked="" type="checkbox"/>
Approval Letter	<input checked="" type="checkbox"/>
Disapproval Letter	<input type="checkbox"/>
COMPLETION DATA:	
Date Well Completed	<u>4-12-62</u>
Location Inspected	<input type="checkbox"/>
OW _____ WW _____ TA _____	Bond released
GW _____ OS _____ (PA <u>6-5-63</u>)	State of Fee Land
	<input type="checkbox"/>
Driller's Log <u>5-18-62</u>	LOGS FILED
Electric Logs (No. <u>2</u>) <input checked="" type="checkbox"/>	
E _____ I _____ E-I _____ GR _____ GR-N _____ Micro _____	
Lat _____ Mi-L _____ Sonic _____ Others <u>Radioactivity Log</u>	

Guard Log
Sub-Surface Directional Survey

(SUBMIT IN DUPLICATE)

LAND: *67964-22*

Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
 State☒
 Lease No. ML 3536
 Public Domain☐
 Lease No.
 Indian☐
 Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well.....	<input checked="" type="checkbox"/> 	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History.....
--	---	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

November 1, 19 61

Spiller Canyon State

Well No. 1 is located 500 ft. from {S} line and 500 ft. from {W} line of Sec. 16

SW SW Sec. 16

30S

25E

S.L.P.M.

(1/4 Sec. and Sec. No.)

(Twp.)

(Range)

(Meridian)

Wildcat

San Juan County

Utah

(Field)

(County or Subdivision)

(State or Territory)

Ground (Ungraded and estimated)

The elevation of the ~~surface~~ above sea level is 6840 feet.A drilling and plugging bond has been filed with U.S. Government
State Land Board
R. H. Massey

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

Proposed Casing Program:

- 75' - 16" OD Conductor casing (Cemented to surface)
- 1,000' - 10-3/4" OD Surface casing (Cemented to surface)
- 10,000' - 5-1/2" OD Production String (Cemented with sufficient cement to meet conditions encountered)

Principal objective: Mississippian

Estimated Total Depth: 10,000'

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil CompanyAddress P. O. Box 265Moab, Utah

By

Robert H. Massey
 Robert H. Massey
 Title Area Land Agent.

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

THE PURE OIL COMPANY

LOCATION REPORT

Spiller Canyon

A.F.E. No. 4522

Date November 1, 1961

Division Northern Producing

Prospect
District

Four Corners Area

Spiller Canyon

Lease State of Utah (M.L. 3536)

Acres 640 Lease No. 8645 Elevation Well No. State 1 (Serial No.)

Quadrangle SW SW Sec. 16 Twp. 30 S Rge. 25 E Bk. Dist. Twp.

Survey S.L.P.M. County San Juan State Utah

Operator The Pure Oil Company Map Utah 1-4

500 Feet East of the West line of Section
 500 Feet North of the South line of Section
 Feet of the line of
 Feet of the line of

LEGEND

○ Location




Gas Well



Oil Well




Gas-Distillate Well



Dry Hole




Abandoned Location




Abandoned Gas Well



Abandoned Oil Well



Input Well



Remarks: The Superior 47-16 and 47-17 and Union 1 holes above indicated as dry holes represent potassium exploration holes.

Scale 2" = 1 MILE

Submitted by *Per Lindholm* Civil Engineer

Approved by _____ Division Manager

Approved by _____ Vice-President—General Manager

November 30, 1961

The Pure Oil Company
P. O. Box 265
Moab, Utah

Attn: Robert H. Massey, Area Land Agent

Gentlemen:

This is to acknowledge receipt of your notice of intention to drill Well No. Spiller Canyon State #1, which is to be located 500 feet from the south line and 900 feet from the west line of Section 16, Township 30 South, Range 25 East, SE1/4, San Juan County, Utah.

Please be advised that approval to drill said well is hereby granted in accordance with the Order issued in Cause No. 71 in a Hearing held on November 29, 1961.

This approval terminates within 90 days if the above mentioned well has not been spudded in within said period.

Please take note that should it be necessary to plug and abandon said well you are hereby requested to give advance notice of the date and time said plugging will take place to one of the following named individuals, by phone or otherwise, in order that our petroleum engineer may be present to inspect the manner in which the well is being plugged:

C. B. FREIGHT, Executive Director
Office Phone: DA 8-5771 or DA 8-5772
Home Phone: HU 5-2721

The Pure Oil Company
Attn: Robert H. Massey

November 30, 1961
Page -2-

ROBERT L. SCHMIDT, Chief Petroleum Engineer
Office Phone: DA 8-5771 or DA 8-5772
Home Phone: AM 6-8616

All other forms of communication should be addressed to
the Utah State Oil and Gas Conservation Commission, 310 Newhouse
Building, Salt Lake City, Utah.

Please have the enclosed "Minimum Safety Requirements"
notice posted in a conspicuous place on the drilling location.

Very truly yours,

OIL & GAS CONSERVATION COMMISSION

CLEON B. FEIGHT,
EXECUTIVE DIRECTOR

CBF:avg
cc: Utah State Land Board
Salt Lake City, Utah

H. L. Coonts - OGCC, Moab

Enclosure

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

State Capitol Building
Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

December 19 **61**

Agent's address P. O. Box 265

Company The Pure Oil Company

Moab, Utah

Signed X-3 Strong

Phone ALpine 3-3581

Agent's title District Chief Clerk

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16 Spiller	30S Canyon	25E State	1 No. 1	Drlg.	-0-	-0-	-0-	Location: 500' FSL and 500' FWL. L & S elevations: GR 6847', KB 6863. Set 20" OD conductor at 15' ground level measurement and cemented with 9 yards of ready mix cement on 12-28-61. Spudded at 5:30 p.m. 12-30-61. Now drilling at 400'.

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSIONState Capitol Building
Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

January, 1962Agent's address P. O. Box 265Company The Pure Oil CompanyMoab, Utah

Signed

J. B. StrongPhone Alpine 3-3581Agent's title District Chief ClerkState Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16 Spiller Canyon State No. 1	30S	25E	1	Drlg.	-0-	-0-	-0-	Drilled from 400' to 1744'. Reamed 8-3/4" hole to 13-3/4" to 1000'. Set 31 jts. of 10-3/4" 32.75# H-40 casing at 1000' KB. Cemented with 350 sax 50-50 Pozmix with 4% gel and 1/4# Flocele and 1# Tufplug added per sack and 2% calcium chloride. Tailed in with 125 sax regular cement with 2% CaCl. Ran 1" pipe down back side of casing. Tagged cement at 45'. Cemented thru 1" pipe with 75 sax regular cement with 3% CaCl with 1# Tufplug and 1/4# Flocele per sack. Drilled from 1744' to 4128'. Lost circulation at 2640', 2654' and 4128'. Mixed mud and regained circulation. On January 19, 1962, well made small gas kick at 4697' and 4718'. Turned mud black and had hydrogen sulfide odor, but gas would not burn. Increased mud weight to 10.3# and drilled to 4830'. Well started blowing mud out of hole. Closed hydril and pressure on drill pipe was 350#. Opened to pit and flowed dry gas. Commenced flowing at rate estimated to be 1000 MCF and decreased to 500 MCF in one hour. Drill pipe stuck at 4824'. Pumped 20 bbls. of fresh water ahead of 500 bbls. of 11.6# mud with 25% lost circulation material. Drilled to 4905' and well began unloading gas cut mud. Mixed mud to 16.6#. Started reaming 8-3/4" hole to 9-7/8" in order to set 7-5/8" casing. Reamed to 1674' and while pulling up to make connection, pipe stuck 31' off bottom. Bit at 1643'. Pumped 200 sax of regular cement with 2% calcium chloride through drill pipe in an effort to plug off lost circulation zone and form cement plug below bit. Backed off drill pipe at 1512', leaving fish from 1512' to 1643'. Began washing over fish on January 31, 1962.

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection



"Symbol of Service"

REPORT of SUB-SURFACE DIRECTIONAL SURVEY

PURE OIL COMPANY
COMPANY

SPILLER CANYON STATE NO. 1
WELL NAME

SAN JUAN COUNTY, UTAH
LOCATION

JOB NUMBER

RS-1362

TYPE OF SURVEY

MULTIPLE SHOT & SINGLE SHOT

DATE

Jan. 7, 1962

SURVEY BY

OFFICE

RECORD OF SURVEY

CHECKED BY_____

JOB NO. RS-1362 DATE January 7, 1962

DATE January 7, 1962

STATION	MEASURED DEPTH		DRIFT ANGLE	TRUE VERTICAL DEPTH		COURSE DEVIATION		DRIFT DIRECTION	RECTANGULAR COORDINATES							
									NORTH		SOUTH		EAST		WEST	
MULTIPLE SHOT SURVEY THROUGH 1487'																
1	75	99	00° 00'					Vertical								
2	173	44	00° 20'				57	N 56° E		32				47		
3	259	99	00° 45'				1 13	N 56° E		95			1	41		
4	349	02	00° 50'				1 29	N 55° E		1 69			2	47		
5	436	02	01° 00'	435	98		1 52	N 55° E		2 56			3	72		
6	523	87	01° 25'				2 17	N 46° E		4 07			5	28		
7	611	57	01° 30'				2 30	N 46° E		5 67			6	93		
8	700	55	01° 35'				2 46	N 51° E		7 22			8	84		
9	795	43	02° 00'				3 31	N 52° E		9 26			11	45		
10	889	83	02° 15'	889	55		3 71	N 48° E		11 74			14	21		
11	984	37	01° 55'				3 16	N 47° E		13 90			16	52		
12	1078	95	02° 20'				3 85	N 45° E		16 62			19	24		
13	1173	20	02° 45'				4 52	N 49° E		19 59			22	65		
14	1267	90	02° 50'				4 68	N 57° E		22 14			26	58		
15	1362	40	03° 10'	1361	60		5 22	N 55° E		25 13			30	86		
16	1455	50	03° 30'				5 68	N 51° E		28 70			35	27		
17	1487	00	03° 50'				2 11	N 50° E		30 06			36	89		
18	1715	00	04° 30'				17 90	N 50° E		41 57			50	60		
19	1801	00	04° 30'				6 75	N 47° E		46 17			55	54		
20	1854	00	04° 30'	1851	81		4 16	N 45° E		49 11			58	48		



RECORD OF SURVEY

JOB NO. RS-1362

DATE January 7, 1962

PAGE 2

CHECKED BY _____

STATION	MEASURED DEPTH		DRIFT ANGLE	TRUE VERTICAL DEPTH		COURSE DEVIATION		DRIFT DIRECTION	RECTANGULAR COORDINATES								
									NORTH		SOUTH		EAST		WEST		
21	1950	00	05° 00'	2300	63	8	37	N 42° E	55	33			64	08			
22	2005	00	04° 45'			4	55	N 42° E	58	71			67	12			
23	2116	00	05° 00'			9	68	N 47° E	65	31			74	20			
24	2210	00	06° 15'			10	24	N 45° E	72	55			81	44			
25	2305	00	06° 45'			11	16	N 42° E	80	84			88	91			
26	2456	00	06° 30'	2826	56	17	09	N 40° E	93	93			99	90			
27	2550	00	06° 15'			10	24	N 40° E	101	77			106	48			
28	2645	00	06° 15'			10	35	N 40° E	109	70			113	13			
29	2739	00	05° 45'			9	42	N 40° E	116	92			119	19			
30	2834	00	06° 00'			9	93	N 40° E	124	53			125	57			
31	2929	00	05° 45'	3280	35	9	52	N 39° E	131	93			131	56			
32	3023	00	05° 30'			9	01	N 35° E	139	31			136	73			
33	3117	00	05° 15'			8	60	N 35° E	146	36			141	66			
34	3195	00	05° 30'			7	47	N 37° E	152	33			146	16			
35	3290	00	06° 15'			10	35	N 32° E	161	11			151	64			
36	3369	00	06° 15'	3702	10	8	60	N 30° E	168	56			155	94			
37	3463	00	06° 00'			9	82	N 27° E	177	31			160	40			
38	3556	00	06° 00'			9	72	N 23° E	186	25			164	20			
39	3651	00	05° 30'			9	10	N 23° E	194	63			167	76			
40	3714	00	05° 45'			6	31	N 26° E	200	30			170	53			
41	3808	00	06° 15'	4114	15	10	24	N 19° E	209	98			173	86			
42	3903	00	06° 00'			9	93	N 18° E	219	42			176	93			
43	3965	00	05° 45'			6	21	N 15° E	225	42			178	54			
44	4059	00	05° 00'			8	20	N 11° E	233	47			180	10			
45	4128	00	04° 30'			5	42	N 10° E	238	81			181	04			



RECORD OF SURVEY

CHECKED BY _____

JOB NO. RS-1362

DATE January 7, 1962

PAGE 3

STATION	MEASURED DEPTH		DRIFT ANGLE	TRUE VERTICAL DEPTH		COURSE DEVIATION		DRIFT DIRECTION	RECTANGULAR COORDINATES									
									NORTH		SOUTH		EAST		WEST			
46	4203	00	04° 45'	4778	98	6	21	N 10° E	244	93			182	12	Direction Interpolated			
47	4392	00	04° 45'			15	65	N 15° E	260	05			186	17				
48	4580	00	05° 15'			17	21	N 16° E	276	59			190	91				
49	4769	00	06° 45'			22	21	N 18° E	297	71			197	77				
50	4796	00	06° 45'			3	17	N 17° E	300	74			198	70				
51	5327	00	06° 45'	5718	12	62	39	N 25° E	357	28			225	07				
52	5416	00	06° 45'			10	46	N 25° E	366	76			229	49				
53	5495	00	06° 00'			8	26	N 32° E	373	76			233	87				
54	5588	00	05° 45'			9	32	N 36° E	381	30			239	35				
55	5741	00	05° 30'			14	66	N 40° E	392	53			248	77				
56	5831	00	05° 30'	6140	40	8	62	N 45° E	398	63			254	87				
57	5880	00	06° 15'			5	34	N 45° E	402	41			258	65				
58	5946	00	05° 30'			6	32	N 49° E	406	56			263	42				
59	6030	00	07° 00'			10	24	N 55° E	412	43			271	81				
60	6166	00	07° 15'			17	16	N 52° E	423	00			285	33				
61	6225	00	07° 15'	6382	66	7	45	N 48° E	427	98			290	87				
62	6259	00	07° 15'			4	29	N 50° E	430	74			294	16				
63	6317	00	07° 00'			7	07	N 47° E	435	56			299	33				
64	6358	00	06° 45'			4	82	N 45° E	438	97			302	74				
65	6410	00	06° 00'			5	43	N 44° E	442	88			306	51				
66	6470	00	05° 30'	6648	87	5	75	N 44° E	447	02			310	50				
67	6532	00	04° 45'			5	13	N 46° E	450	58			314	19				
68	6590	00	04° 00'			4	05	N 40° E	453	68			316	79				
69	6654	00	03° 30'			3	90	N 40° E	456	67			319	30				
70	6677	00	03° 30'			1	40	N 40° E	457	74			320	20				



RECORD OF SURVEY

CHECKED BY _____

JOB NO. RS-1362


DATE January 7, 1962


PAGE 4

STATION	MEASURED DEPTH		DRIFT ANGLE	TRUE VERTICAL DEPTH		COURSE DEVIATION		DRIFT DIRECTION	RECTANGULAR COORDINATES							
									NORTH		SOUTH		EAST		WEST	
71	6744	00	03° 45'			4	38	N 45° E	460	84			323	30		
72	6807	00	03° 45'			4	12	N 47° E	463	65			326	31		
73	6868	00	04° 15'			4	52	N 45° E	466	85			329	51		
74	6957	00	04° 15'			6	59	N 40° E	471	90			333	75		
75	7021	00	04° 15'	6992	03	4	74	N 43° E	475	37			336	98		
76	7052	00	04° 15'			2	30	N 45° E	477	00			338	61		
77	7115	00	04° 30'			4	95	N 42° E	480	68			341	92		
78	7151	00	04° 45'			2	98	N 48° E	482	67			344	13		
79	7208	00	04° 45'			4	72	N 49° E	485	77			347	69		
80	7273	00	04° 00'	7243	28	4	54	N 48° E	488	81			351	06		
81	7400	00	10° 00'			22	05	N 60° E	499	84			370	16		
82	7600	00	07° 30'			26	10	N 73° E	507	47			395	12		
83	7892	00	07° 00'			35	59	N 80° E	513	65			430	17		
	7975	00	05° 45'			8	32	N 83° E	514	66			438	43		
85	8200	00	04° 30'	8163	33	17	66	N 79° E	518	03			455	77		
86	8450	00	04° 00'			17	45	N 75° E	522	55			472	62		
87	8700	00	02° 00'			8	73	S 87° E	522	09			481	34		
88	8900	00	01° 30'			5	24	S 35° E	517	80			484	35		
89	8933	00	01° 45'			1	01	S 20° E	516	85			484	70		
90	9100	00	02° 15'	9062	37	6	56	S 20° E	510	69			486	94		
91	9407	00	01° 45'			9	36	S 32° E	502	75			491	89		
92	9450	00	01° 45'	9412	20	1	31	N 39° E	503	77			492	71		
CLOSURE 704.66' N 44° 22' E																




SCALE
1" = 50'





EASTMAN
OIL WELL
SURVEY COMPANY

JOB N° RS-1362



STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill.....	Subsequent Report of Water Shut-off.....	
Notice of Intention to Change Plans.....	Subsequent Report of Altering Casing.....	
Notice of Intention to Redrill or Repair.....	Subsequent Report of Redrilling or Repair.....	
Notice of Intention to Pull or Alter Casing.....	Supplementary Well History.....	X
Notice of Intention to Abandon Well.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

January 3, 19 62

Spiller Canyon State
Well No. 1 is located 500 ft. from {S} line and 500 ft. from {W} line of Sec. 16

SW SW Sec. 16 30S 25E S.L.P.M.
(¼ Sec. and Sec. No.) (Twp.) (Range) (Meridian)

Wildecatt San Juan County Utah
(Field) (County or Subdivision) (State or Territory)

Ground (Ungraded and estimated)

The elevation of the ~~surface~~ above sea level is 6840 feet.

A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)


12-28-61 Set 1 jts. (15') of 20" OD casing at 15' ground level measurement.
Cemented with ready mix cement.

Spudded 12-30-61 at 5:30 p.m. Now drilling at 787' - Inc.

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company
Address P. O. Box 265 By J. B. Strong
Moab, Utah Title District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill.....	Subsequent Report of Water Shut-off.....	
Notice of Intention to Change Plans.....	Subsequent Report of Altering Casing.....	
Notice of Intention to Redrill or Repair.....	Subsequent Report of Redrilling or Repair.....	
Notice of Intention to Pull or Alter Casing.....	Supplementary Well History.....	X
Notice of Intention to Abandon Well.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

January 15, 1962

Spiller Canyon State

Well No. 1 is located 500 ft. from KS line and 500 ft. from W line of Sec. 16

SW SW Sec. 16

(¼ Sec. and Sec. No.)

30S

(Twp.)

25E

(Range)

S.L.P.M.

(Meridian)

Wildcat

(Field)

San Juan County

(County or Subdivision)

Utah

(State or Territory)

The elevation of the ~~surface~~ ground above sea level is 6847 feet. KB elevation 6863' L & S elevations

A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

Drilled 8-3/4" hole to 1744'. Reamed to 13-3/4" to 1000'. Ran 31 jts. of 10-3/4" OD 32.75# H-40 casing, set at 1000' KB. Float set at 967'. Unable to circulate after running pipe. Pumped in 270 bbls. of mud with 22% lost circulation material. Recovered circulation. Circulated 45 minutes before cementing. Cemented with 350 sax 50-50 Pozmix, 4% gel, 1/4# Flocele, 1# Tufplug added per sack, also 2% calcium chloride. Tailed in with 125 sax regular with 2% calcium chloride. Pumping cement at rate of 1 bbl. per minute, 70 bbls. of displacement in and lost circulation. Plug down at 12:30 a.m. 1-10-62. Ran 1" pipe down back-side of casing. Found cement at 45' from KB. Cemented thru 1" pipe with 75 sax regular cement with 3% calcium chloride with 1# Tufplug and 1/4# Flocele per sack. Job complete at 9:00 a.m. 1-10-62.

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company

Address P. O. Box 265

Moab, Utah

By

Title

J. B. Strong
J. B. Strong
District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSIONState Capitol Building
Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for


February, 19 62.Agent's address P. O. Box 265
Moab, UtahCompany The Pure Oil CompanySigned J.B. StrongPhone ALpine 3-3581Agent's title District Chief ClerkState Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & 1/4 of 1/4	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16 Spiller Canyon State No. 1	30S	25E	1	Drlg.	-0-	-0-	-0-	Washed over fish to 1,559'. Unable to get below 1,573'. Screwed back into fish to run free point. Could not get below 1,568'. Ran Dialog clean up tool and Backed off fish at 1,543'. Recovered 1 - 7" drill collar and 1 - 3" change over sub, 7" to 8". Ran 9" wash pipe with clusterite shoe and washed from 1,543' to 1,602'. Backed off fish at 1,600' and recovered 2 - 8" drill collars, leaving 1 - 8" drill collar, shock sub, reamer and bit in hole. Wash to 1,643'. Ran McCullough clean out tool and cleaned out fish from 1,612' to bit. Screwed into fish at 1,600'. Backed off at 1,639'. Recovered 8" drill collar and shock sub. Screwed into fish and attempted to jar fish loose. Unable to do so. Backed off at 1,636'. Washed over to 1,646'. Picked up overshot and recovered fish on 2-13-62. Reamed 8-3/4" hole to 9-7/8" to 4,905' and drilled new hole to 5,155'. Ran 166 fts. of 7-5/8" 29.70# casing, set at 5,155'. Cemented with 400 sax 50-50 Pozmix, salt saturated and with 2% gel, and 500 sax regular salt saturated cement with 1/4# Flecele per sack. Plug down at 8:15 p.m. 2-27-62. Now W.O.C. and nipping up.

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill.....		Subsequent Report of Water Shut-off.....	
Notice of Intention to Change Plans.....	<input checked="" type="checkbox"/>	Subsequent Report of Altering Casing.....	
Notice of Intention to Redrill or Repair.....		Subsequent Report of Redrilling or Repair.....	
Notice of Intention to Pull or Alter Casing.....		Supplementary Well History.....	
Notice of Intention to Abandon Well.....			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

February 8, 19 62

Spiller Canyon State

Well No. 1 is located 500 ft. from SW line and 500 ft. from W line of Sec. 16

SW SW Sec. 16
(¼ Sec. and Sec. No.)

30S
(Twp.)

25E
(Range)

SLEM
(Meridian)

Wildcat
(Field)

San Juan County
(County or Subdivision)

Utah
(State or Territory)

The elevation of the ~~surface~~ ground above sea level is 6847 feet. KB elevation 6863'.

A drilling and plugging bond has been filed with State Land Board.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

SEE SUPPLEMENTAL SHEET ATTACHED

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company

Address P. O. Box 265
Moab, Utah

By J. B. Strong
Title District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.


SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Change Plans
Spiller Canyon State No. 1

February 8, 1962

Propose to change the casing program to include setting of 7-5/8" Intermediate casing at approximately 5300' with sufficient cement to meet conditions encountered for the reason shown below:

Drilled from 1744' to 4128'. Lost circulation at 2640', 2654' and 4128'. Mixed mud and regained circulation. On January 19, 1962, well made small gas kick at 4697' and 4718'. Turned mud black and had hydrogen sulfide odor, but gas would not burn. Increased mud weight to 10.3# and drilled to 4830'. Well started blowing mud out of hole. Closed hydril and pressure on drill pipe was 350#. Opened to pit and flowed dry gas. Commenced flowing at rate estimated to be 1000 MCF and decreased to 500 MCF in one hour. Drill pipe stuck at 4824'. Pumped 20 bbls. of fresh water ahead of 500 bbls. of 11.6# mud with 25% lost circulation material. Worked drill pipe loose. Killed well with 13# mud with 25% lost circulation material. Drilled to 4905' and well began unloading gas cut mud. Mixed mud to 16.6#. Started reaming 8-3/4" hole to 9-7/8" in order to set 7-5/8" casing. Reamed to 1674' and while pulling up to make connection, pipe stuck 31' off bottom. Bit at 1643'. Pumped 200 sax of regular cement with 2% calcium chloride through drill pipe in an effort to plug off lost circulation zone and form cement plug below bit. Backed off drill pipe at 1512', leaving fish from 1512' to 1643'. Began washing over fish on January 31, 1962. Washed down to 1573'. Screwed back in fish to run free point but could not get below 1568'. Ran Dialog clean up tool and cleaned out on inside of drill pipe to 1590'. Backed off at 1543'. Recovered 1 - 7" drill collar and 1 - 3' change over sub. Washed over from 1543' to 1602'. Backed off fish at 1600' and recovered 2 - 8" drill collars, leaving 1 - 8" drill collar, shock sub, reamer and bit in hole. Washed over fish from 1600' to 1643'. Now rigging up McCullough jet string to clean out drill pipe from 1600' to bit, in order to back off. After fish is recovered, plan to continue reaming hole and set 7-5/8" casing at approximately 5300' with sufficient cement to meet conditions encountered.



STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well.....	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History.....
--	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

February 28, 19 62

Spiller Canyon State
 Well No. 1 is located 500 ft. from SW line and 500 ft. from W line of Sec. 16
SW SW, Sec. 16 30S 25E S.L.B.M.
(¼ Sec. and Sec. No.) (Twp.) (Range) (Meridian)
Wildest San Juan Utah
(Field) (County or Subdivision) (State or Territory)

The elevation of the ~~surface~~ ^{ground} above sea level is 6847 feet. KB elevation 6861 feet.

A drilling and plugging bond has been filed with

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

SEE SUPPLEMENTAL SHEET ATTACHED

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company

Address P. O. Box 265

Meab, Utah

By

J. B. Strong

J. B. Strong

Title District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

Spiller Canyon State No. 1
500' FSL and 500' FWL
SW SW Sec. 16, 30S, 25E
San Juan County, Utah

February 28, 1962
Supplementary Well History


Ran McCullough clean out tool. Cleaned out fish from 1612' to bit at 1643'. Backed off at 1639'. Recovered 8" drill collar and shock sub, leaving 9-7/8" bit and Drilco reamer in hole. Washed over fish to 1642'. Ran Clustrite was over shoe and washed over fish from 1642' to 1646'. Picked up overshot and recovered all of fish. Circulated and conditioned mud after recovering fish. No junk in hole. Drilled cement from 1646' to 1674'. Reamed 8-3/4" hole to 9-7/8" from 1674' to present depth of 4905' and drilled 9-7/8" hole to 5155'.

2-26-62 Ran Welex Gamma Ray Acoustic and Guard Log to 5155'.

2-27-62 Ran 166 jts. of 7-5/8" 29.70# casing (5163.46'). (131 jts. Deepwell P-110 29.70#, 35 jts. N-80 29.70#) set at 5155'. Cemented with 400 sax of 50-50 Pozmix, salt saturated, with 2% gel and 500 sax regular salt saturated cement with 1/4# Flocele per sack. Cement circulated at surface. Plug down at 8:15 p.m. Released pressure, plug holding. Pressured up to 600# and shut in. Job complete at 8:20 p.m. 2-27-62. Now preparing to cut off.

Copy to AC
(SUBMIT IN DUPLICATE)

LAND:



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill.....	Subsequent Report of Water Shut-off.....	
Notice of Intention to Change Plans.....	Subsequent Report of Altering Casing.....	
Notice of Intention to Redrill or Repair.....	Subsequent Report of Redrilling or Repair.....	
Notice of Intention to Pull or Alter Casing.....	Supplementary Well History.....	<input checked="" type="checkbox"/>
Notice of Intention to Abandon Well.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

Spiller Canyon State
Well No. 1 is located 500 ft. from {N} line and 500 ft. from {W} line of Sec. 16
SW SW Sec. 16 30S 25E S.L.B.M.
($\frac{1}{4}$ Sec. and Sec. No.) (Twp.) (Range) (Meridian)
Wildcat San Juan County Utah
(Field) (County or Subdivision) (State or Territory)

The elevation of the ~~surface~~ ground above sea level is 6847 feet. KB elevation 6863'

A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

SEE SUPPLEMENTAL SHEET ATTACHED

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company
Address P. O. Box 265
Moab, Utah
By J. El Strong
Title District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

Spiller Canyon State No. 1
500' FSL and 500' FWL
SW SW Sec. 16, 30S, 25E
San Juan County, Utah

February 28, 1962
Supplementary Well History

Ran McCullough clean out tool. Cleaned out fish from 1612' to bit at 1643'. Backed off at 1639'. Recovered 8" drill collar and shock sub, leaving 9-7/8" bit and Drilco reamer in hole. Washed over fish to 1642'. Ran Clustrite wash over shoe and washed over fish from 1642' to 1646'. Picked up overshot and recovered all of fish. Circulated and conditioned mud after recovering fish. No junk in hole. Drilled cement from 1646' to 1674'. Reamed 8-3/4" hole to 9-7/8" from 1674' to present depth of 4905' and drilled 9-7/8" hole to 5155'.

2-26-62 Ran Welex Gamma Ray Acoustic and Guard Log to 5155'.

2-27-62 Ran 166 jts. of 7-5/8" 29.70# casing (5163.46'). (131 jts. Deepwell P-110 29.70#, 35 jts. N-80 29.70#) set at 5155'. Cemented with 400 sax of 50-50 Pozmix, salt saturated, with 2% gel and 500 sax regular salt saturated cement with 1/4# Flocele per sack. Plug down at 8:15 p.m. Released pressure, plug holding. Pressured up to 600# and shut in. Job complete at 8:20 p.m. 2-27-62. Now preparing to cut off.

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

March, 1962.Agent's address P. O. Box 265Company The Pure Oil CompanyMoab, UtahSigned J.B. StrongPhone Alpine 3-3581Agent's title District Chief ClerkState Lease No. ML 3536

Federal Lease No. _____

Indian Lease No. _____


Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16 Spiller Canyon State No. 1	30S	25E	1	Drlg.	-0-	-0-	-0-	Drilled from 5,155' to 9,400'. DST No. 1 9,260' - 9,400'. Drilled to 9,450'. DST No. 2 9,398' - 9,450'. Drilled to TD of 9,661'. Drilling com- pleted 4-9-62. Ran electric logs to T.D. Well temporarily abandoned as follows: Plug No. 1 - 9,475' - 9,425' - 50' - 25 Plug No. 2 - 9,275' - 9,025' - 250' - 50 Plug No. 3 - 5,300' - 5,000' - 300' - 50 sax salt saturated cement with 4% gel. sax salt saturated cement with 4% gel. sax salt saturated cement with 4% gel. Left 10.7# mud between plugs. Installed flange, 10" x 2" swadge and a 2" valve bolted on top of casing bowl. Rig released at 4:00 p.m. 4-12-62. FINAL REPORT until work is resumed.

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
 SALT LAKE CITY, UTAH

Fee and Patented.....☐
 State.....☒
 Lease No. ML 3536
 Public Domain.....☐
 Lease No.
 Indian.....☐
 Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well.....	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History.....
--	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

April 2, 1962

Spiller Canyon State

Well No. 1 is located 500 ft. from {S} line and 500 ft. from {W} line of Sec. 16SW SW Sec. 16
(¼ Sec. and Sec. No.)30S
(Twp.)25E
(Range)S.L.B.M.
(Meridian)

Wildcat

(Field)

San Juan

(County or Subdivision)

Utah

(State or Territory)

ground

The elevation of the ~~surface~~ surface above sea level is 6847 feet. KB elevation 6861'. This is 2' correction.A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

Drilled to 9400'. DST No. 1 - 9260' - 9400' Tool open 70 minutes. Opened with fair blow. Gas to surface in 60 minutes. Gas too small to measure. Recovered 270' gas cut mud. Pressures: IH 5060#; 45 minute ICI 1520#; IF 165#; FF 255#; 45 minute FCI 2080#; FH 5040#. Bottom hole temperature 154°.

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.


Company The Pure Oil CompanyAddress P. O. Box 265Moab, Utah

By

Title

J. B. Strong
 J. B. Strong
 District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
 SALT LAKE CITY, UTAH

Fee and Patented.....☐
 State☒
 Lease No. ML 3536
 Public Domain☐
 Lease No.
 Indian☐
 Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well.....	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History.....
--	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

April 4, 1962

Spiller Canyon State
 Well No. 1 is located 500 ft. from {N} line and 500 ft. from {W} line of Sec. 16
SW SW Sec. 16 30S 25E S.L.B.M.
(¼ Sec. and Sec. No.) (Twp.) (Range) (Meridian)
Wildcat San Juan Utah
(Field) (County or Subdivision) (State or Territory)

The elevation of the ~~surface~~ ground above sea level is 6847 feet. KB elevation 6861'.

A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

4-3 & 4-62 Drilled to 9450'. DST No. 2 - 9398' - 9450' Tool open 65 minutes. Very weak blow throughout. Recovered 950' of slightly gas cut salt water. Pressures: IH 5140#; 45 minute ICI 3050#; IF 170#; FF 390#; 45 minute FCI 480#; FH 5120#. Bottom hole temperature 154°.

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil Company

Address P. O. Box 265

Moab, Utah

By

J. B. Strong

Title

District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

April, 19 62Agent's address P. O. Box 265 Company THE PURE OIL COMPANYMoab, UtahSigned J.B. StrongPhone Alpine 3-3581 Agent's title District Chief ClerkState Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

4/10
April 10, 1962

MEMO FOR FILING

Re: Pure Oil Company
Spiller Canyon State #1
Sec. 16, T. 30 S, R. 25 E.,
San Juan County, Utah


On April 9, 1962, I approved the following plugging procedure on the above well.

The operator plans to plug back and attempt to obtain production by perforating in the Paradox Salt.

T.D. 9625'
Mississippian 9269'
Bottom Paradox Salt 9136'
Run 50' plug across DST @ 9450'.
225' plug at 9050-9275' across Mississippian and
bottom of Paradox.
100' across bottom of 7 5/8" casing @ 5155'.

HARVEY L. COONTS
PETROLEUM ENGINEER

HLC:cn



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
 State☒
 Lease No. ML 3536
 Public Domain☐
 Lease No.
 Indian☐
 Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well Temporarily <input checked="" type="checkbox"/>	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History.....
---	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

April 12, 19 62

Spiller Canyon State

Well No. 1 is located 500 ft. from {N} line and 500 ft. from {E} line of Sec. 16

SW SW Sec. 16 30S 25E S.L.B. & M.
(¼ Sec. and Sec. No.) (Twp.) (Range) (Meridian)

Wildcat San Juan Utah
(Field) (County or Subdivision) (State or Territory)

ground

The elevation of the ~~derrick base~~ above sea level is 6,847 feet. KB elevation 6,861'.

A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

SEE SUPPLEMENTAL SHEET ATTACHED

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company The Pure Oil CompanyAddress P. O. Box 265Moab, Utah

By

Title

J. B. Strong
District Chief Clerk

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

Notice of Intention to Temporarily Abandon Well

April 12, 1962

Spiller Canyon State No. 1
SW SW, Sec. 16, 30S, 25E, San Juan County, Utah

State Lease
No. ML 3536

Drilled from 9,450' to 9,661' TD. Drilling completed at 8:30 a.m. 4-9-62.

Ran electric logs to total depth.

LOG TOPS

TVD

Base of Salt	9,132'	9,044' (-2235')
? Molas	9,214'	9,176' (-2315')
Mississippian	9,247'	9,209' (-2343')
Ouray	9,652'	9,614' (-2753')

Ran cement plugs in bottom of hole as follows:

Plug No. 1 - 9,475' - 9,425' - 50' - Miss.	25 sax salt saturated cement with 4% gel.
Plug No. 2 - 9,275' - 9,025' - 250' - Base of salt to Miss.	50 sax salt saturated cement with 4% gel.
Plug No. 3 - 5,300' - 5,000' - 300' - Bottom of 7-5/8" casing	50 sax salt saturated cement with 4% gel.

Propose to temporarily abandon well by leaving 10.7# mud inside of 7-5/8" casing from the cement plug at 5,000' to surface. Will install flange and valve on top of casing head in order that well may be temporarily abandoned.

The drilling of this well extends the primary lease for two years and it is possible that we will want to reenter this well at a later date.



THE PURE OIL COMPANY

NORTHERN PRODUCING DIVISION • Four Corners District

P. O. BOX 265 • MOAB, UTAH • ALPINE 3-3581

April 13, 1962

Mr. C. B. Feight
Oil & Gas Conservation Commission
310 Newhouse Building
10 Exchange Place
Salt Lake City 11, Utah

Dear Mr. Feight:

As per our phone conversation on April 13, 1962 concerning our well, Spiller Canyon State No. 1, located SW SW, Section 16-30S-25E, San Juan County, Utah. We would like to have the information be held in the "Confidential File", especially on the Log Tops, which was submitted to your office on a "Notice of Intention to Temporarily Abandon" dated April 12, 1962.

Thank you very much for your help and information.

Yours very truly,

THE PURE OIL COMPANY

J. W. Burnside
J. W. Burnside
Clerk

/jb

THE SUPERIOR OIL COMPANY

MINERALS DIVISION
P. O. BOX 600
DENVER 1, COLORADO

May 1, 1962

Mr. Cleon B. Feight
Executive Director
The State of Utah Oil and Gas
Conservation Commission
Salt Lake City 11, Utah

Dear Mr. Feight:


In regard to the Spiller Canyon #1 State which was drilled recently by Pure Oil in Section 16, T.30S, R.25E, San Juan County, Utah, I wish to inform you of the following occurrences of potash in said well as indicated by the gamma-acoustic velocity log:

- (1) The bed which we normally refer to as the Lower Potash Bed occurs in the interval 2080-2086' in salt cycle 9 (of Hite).
- (2) A carnallite zone occurs in salt cycle 10 (of Hite) in the interval 2130-2140'.
- (3) A potash bed which occurs over the greater part of the Paradox Basin in salt cycle 19 (of Hite) is present in the interval 3230-3310'. This potash bed, according to Hite, contains, by volume, more potash than any other potash bed in the Paradox formation.

I am furnishing this information with the thought that should it be necessary to plug this well proper measures will be taken to protect the potash. Superior does hold a Utah State lease on this Section 16.

Very truly yours,

THE SUPERIOR OIL COMPANY




Ralph H. Wilpolt
Manager, Minerals Division

RHW/jmw

RLL
13

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City, Utah



LOCATE WELL CORRECTLY

To be kept Confidential until ~~February 2, 1962~~
(Not to exceed 4 months after filing date)

LOG OF OIL OR GAS WELL

Operating Company The Pure Oil Company Address P.O. Box 265 - Moab, Utah
 Lease or Tract: The Pure Oil Company Field Wildcat State Utah
Spiller Canyon State
 Well No. 1 Sec. 16 T. 30S R. 25E Meridian S.L.P.M. County San Juan KE 6861'
 Location 500 ft. N. of S. Line and 500 ft. E. of W. Line of SW SW, Sec. 16 Elevation Gr. 6847'
(Derrick floor relative to sea level)

The information given herewith is a complete and correct record of the well and all work done thereon so far as can be determined from all available records.

Date May 17, 1962 Signed J. B. Strong Title District Chief Clerk

The summary on this page is for the condition of the well at above date.

Commenced drilling December 30, 1961 Finished drilling April 9, 1962

OIL OR GAS SANDS OR ZONES

(Denote gas by G)

No. 1, from None to _____ No. 4, from _____ to _____
 No. 2, from _____ to _____ No. 5, from _____ to _____
 No. 3, from _____ to _____ No. 6, from _____ to _____

IMPORTANT WATER SANDS

No. 1, from None to _____ No. 3, from _____ to _____
 No. 2, from _____ to _____ No. 4, from _____ to _____

CASING RECORD

Size casing	Weight per foot	Threads per inch	Make	Amount	Kind of shoe	Cut and pulled from	Perforated		Purpose
							From—	To—	
20"	91#	8-V	SS	15'	Coupling				Cemented to surface.
10-3/4"	32.75#	8-R	SS	1000'	Float				"
7-5/8"	29.70#	8-R	SS	5155'	Float				Intermediate String

MUDDING AND CEMENTING RECORD

Size casing	Where set	Number sacks of cement	Method used	Mud gravity	Amount of mud used
20"	15'	9 yds Ready Mix	Gravity		
10-3/4"	1000'	550 sx	Halliburton		
7-5/8"	5155'	900 sx	Halliburton		

PLUGS AND ADAPTERS

Heaving plug—Material _____ Length _____ Depth set _____
 Adapters—Material _____ Size _____

SHOOTING RECORD

FOLD MARK

MARK
FOLD

Size casing	Where set	Number sacks of cement	Method used	Mud gravity	Amount of mud used
20"	15'	9 yds Ready Mix	Gravity		
10-3/4"	1000'	550 sx	Halliburton		
7-5/8"	5155'	900 sx	Halliburton		

PLUGS AND ADAPTERS

Heaving plug—Material _____ Length _____ Depth set _____

Adapters—Material _____ Size _____

SHOOTING RECORD

Size	Shell used	Explosive used	Quantity	Date	Depth shot	Depth cleaned out

TOOLS USED

Rotary tools were used from zero feet to 9,661 feet, and from _____ feet to _____ feet

Cable tools were used from _____ feet to _____ feet, and from _____ feet to _____ feet

DATES

~~Temporarily Abandoned~~
Date ~~April 12,~~ _____, 1962 Put to producing _____, 19____

The production for the first 24 hours was _____ barrels of fluid of which _____% was oil; _____% emulsion; _____% water; and _____% sediment. Gravity, °Bé. _____

If gas well, cu. ft. per 24 hours _____ Gallons gasoline per 1,000 cu. ft. of gas _____

Rock pressure, lbs. per sq. in. _____

EMPLOYEES

_____, Driller _____, Driller

_____, Driller _____, Driller

FORMATION RECORD

FROM—	TO—	TOTAL FEET	FORMATION
			At the end of complete Driller's Log add Geologic Tops. State whether from Electric Logs or samples.
-0-	912'	912'	Sand and shale.
912'	945'	33'	XX Limestone.
945'	1354'	409'	Lime and shale.
1354'	1744'	390'	Lime and anhydrite.
1744'	3976'	2232'	Salt.
3976'	4128'	152'	Dolomite stringers in salt.
4128'	5722'	1594'	Salt.
5722'	6295'	573'	Salt and shale.
6295'	6734'	439'	Salt.
6734'	7309'	575'	Salt and shale.
7309'	7364'	55'	Salt.
7364'	7373'	9'	Shale.
7373'	7862'	489'	Salt.
7862'	7951'	89'	Salt, shale and dolomite.
7951'	8010'	59'	Salt, shale and anhydrite.
8010'	8627'	617'	Salt.
8627'	8900'	273'	Salt and shale.
8900'	8945'	45'	Limestone and shale.
8945'	9026'	81'	Salt, shale small amounts of limestone.
9026'	9082'	56'	Lime and shale.
9082'	9163'	81'	Salt, shale, dolomite and anhydrite.
9163'	9205'	42'	Lime and shale.
9205'	9254'	49'	Lime, shale and anhydrite.

[OVER]

FORMATION RECORD—Continued

FROM—	TO—	TOTAL FEET	FORMATION
9254'	9303'	49'	Lime and shale.
9303'	9450'	147'	Limestone.
9450'	9500'	50'	Lime.
9500'	9532'	32'	Lime and chert.
9532'	9611'	79'	Limestone.
9611'	9661'	50'	Lime and chalk.
		9661'	TOTAL DEPTH

DST No. 1, 9260' - 9400'. Tool open 70 minutes. Opened with fair blow. Gas to surface in 60 minutes. Burns 10" flame. Recovered 270' gas cut mud. Gas too small to measure. Pressures: (Bottom Bomb) IH 5060, 45 minute ICI 1520, IF 165, FF 255, 45 minute FCI 2080, FH 5040. Bottom hole temperature 154°.

DST No. 2, 9398' - 9450'. Tool open 65 minutes. Very weak blow throughout. Recovered 950' of slightly gas cut salt water. Pressures: IH 5140, 45 minute ICI 3050, IF 170, FF 390, 45 minute FCI 480, FH 5120. Bottom hole temperature 154°.

LOG TOPS

Base of Salt	9132'	True vertical depth 9044'	(-2235)
? Molas	9214'	True vertical depth 9176'	(-2315)
Mississippian	9247'	True vertical depth 9209'	(-2343)
Ouray	9652'	True vertical depth 9614'	(-2753)

Plugged back to 5000' as follows:

Plug No. 1	9475' - 9425'	- 50'	- 25 sx salt cement with 4% Gel.
Plug No. 2	9275' - 9025'	- 250'	- 50 sx salt cement with 4% Gel.
Plug No. 3	5300' - 5000'	- 300'	- 50 sx salt cement with 4% Gel.

(Left 10.7 lb mud at 80 Viscosity between cement plugs.)

Installed Flange, 10" x 2" Swedge and a 2" valve, bolted on to top of Casing Bowl.
Well Temporarily Abandoned ~~May~~ April 12, 1962.



THE PURE OIL COMPANY

NORTHERN PRODUCING DIVISION • Four Corners District

P. O. BOX 265 • MOAB, UTAH • ALPINE 3-3581

May 17, 1962

Spiller Canyon State No. 1
SW SW, Sec. 16-30S-25E
San Juan County, Utah

Mr. C. B. Feight
Oil & Gas Conservation Commission
310 Newhouse Building
10 Exchange Place
Salt Lake City 11, Utah

Dear Mr. Feight:

We wrote you a letter on April 13, 1962, on keeping Spiller Canyon State No. 1, in the "Confidential File". As of this date, this well need not be held confidential. Thank you for your assistance very much.

Attached are the Log of Oil or Gas Well, Electric Logs and a Eastman Directional Survey Report, on the above mentioned well.

Yours very truly,

THE PURE OIL COMPANY

J. B. Strong
J. B. Strong
District Chief Clerk

/jb

Attachments

Copy H. L. C.

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

May and June 1962

Agent's address P. O. Box 265 Company THE PURE OIL COMPANY

Moab, Utah

Signed X B. Strong

Phone ALpine 3-3581 Agent's title Senior District Clerk

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

..... July 1962

Agent's address P. O. Box 1338

Company THE PURE OIL COMPANY

Moab, Utah

Signed

Phone 253-3581

Agent's title District Office Manager

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

Copy H. L. L.
STATE OF UTAH
OIL & GAS CONSERVATION COMMISSIONState Capitol Building
Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

October, 19 62.Agent's address P. O. Box 1338 Company THE PURE OIL COMPANYMoab, UtahSigned [Signature]Phone 253-3581 Agent's title District Office ManagerState Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

U6

Copy H. L. C.

PMB
7

Form OGCC 4

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

November, 1962

Agent's address P. O. Box 1338

Company THE PURE OIL COMPANY

Moab, Utah

Signed

Phone 253-3581

Agent's title District Office Manager

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

December, 1962Agent's address P. O. Box 1338Company THE PURE OIL COMPANYMoab, UtahSigned *L. H. Oggs*Phone 253-3581Agent's title District Office ManagerState Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

Copy H.L.C.
STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for
January, 1963

Agent's address P. O. Box 1338 Company THE PURE OIL COMPANY

Moab, Utah Signed [Signature]

Phone 253-3581 Agent's title District Office Manager

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided
for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

April....., 1963..

Agent's address P. O. Box 1338

Company THE PURE OIL COMPANY

Moab, Utah

Signed

Phone 253-3581

Agent's title District Office Manager

State Lease No. ML-3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30/S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

May 19 63

Agent's address P. O. Box 1338

Company THE PURE OIL COMPANY

Moab, Utah

Signed

Phone 253-3581

Agent's title District Office Manager

State Lease No. **ML 3536** Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	TA	-0-	-0-	-0-	

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection



8710
Z

THE PURE OIL COMPANY

NORTHERN PRODUCING DIVISION • MOAB DISTRICT
P. O. BOX 1338 • MOAB, UTAH • PHONE 253-3581

June 5, 1963

Mr. Cleon B. Feight, Executive Secretary
Utah Oil and Gas Conservation Commission
310 Newhouse Building
10 Exchange Place
Salt Lake City 11, Utah

Dear Jack:

Enclosed is the Sundry Notice for plugging of our Spiller Canyon State No. 1 well, located in the SW SW, Sec. 16, Twp. 30S, Rge. 25E, San Juan County, Utah.


As you know, this well was temporarily abandoned in April, 1962. The Log of Oil or Gas Well was submitted to your office in May, 1962, showing the well as temporarily abandoned. To eliminate filing a revised Log of Oil or Gas Well, perhaps your office could put the additional information shown on the enclosed Sundry Notice on the previously submitted Log of Oil or Gas Well.

Yours very truly,

THE PURE OIL COMPANY

John B. Strong
Senior District Clerk

4



Sec. 16

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION
SALT LAKE CITY, UTAH

Fee and Patented.....☐
State☒
Lease No. ML 3536
Public Domain☐
Lease No.
Indian☐
Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well.....	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History..... Supplementary Notice of Abandonment..... <input checked="" type="checkbox"/>
--	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

June 5, 1963

Spiller Canyon State

Well No. 1 is located 500 ft. from {S} line and 500 ft. from {E} line of Sec. 16SW SW Sec. 16
(¼ Sec. and Sec. No.)30S
(Twp.)25E
(Range)S.L.B. & M.
(Meridian)Wildcat
(Field)San Juan
(County or Subdivision)Utah
(State or Territory)The elevation of the ~~correlation~~ ground above sea level is 6,847 feet. KB elevation 6,861'A drilling and plugging bond has been filed with State Land Board

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

6-5-63 Removed Bradenhead and put 10' cement plug (5 sax regular cement) in top of intermediate casing. Installed dry hole marker in accordance with State of Utah regulations. Well P & A.

This well was temporarily abandoned 4-9-62 as reported on Sundry Notice dated 4-12-62.

10.7# mud left in casing from plug at 5,000' back to surface. ✓

7-5/8" 29.70# casing set at 5,155', through high pressure blow out zone, and cemented back to surface casing. ✓

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.

Company THE PURE OIL COMPANYAddress P. O. Box 1338Moab, Utah

By J. K. Coggan
Title District Office Manager

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

STATE OF UTAH
OIL & GAS CONSERVATION COMMISSION

Salt Lake City 14, Utah

REPORT OF OPERATIONS AND WELL STATUS REPORT

State Utah County San Juan Field or Lease Spiller Canyon State No. 1

The following is a correct report of operations and production (including drilling and producing wells) for

June, 1963.

Agent's address P. O. Box 1338 Company THE PURE OIL COMPANY

Moab, Utah

Signed [Signature]

Phone 253-3581 Agent's title District Office Manager

State Lease No. ML 3536 Federal Lease No. _____ Indian Lease No. _____ Fee & Pat. ☐

Sec. & ¼ of ¼	Twp.	Range	Well No.	*Status	Oil Bbls.	Water Bbls.	Gas MCF's	REMARKS (If drilling, Depth; if shut down, Cause; Date & Results of Water Shut-Off Test; Contents of Gas; and Gas-Oil Ratio Test)
SW SW Sec. 16	30S	25E	1	A	-0-	-0-	-0-	6-5-63: Removed bradenhead, put 10' cement plug (5 sacks regular cement) in top of intermediate string. Installed dry hole marker in accordance with State of Utah regulations. 10.7# mud left in casing from plug at 5,000' back to surface. 7-5/8" 29.70# casing set at 5,155', through high pressure blow out zone, and cemented back to surface casing. Well P & A 6-5-63. <u>FINAL REPORT</u>

NOTE: Report on this form as provided for in Rule C-22. (See back of form.)

FILE IN DUPLICATE

*STATUS: F-Flowing P-Pumping GL-Gas Lift
SI-Shut In D-Dead
GI-Gas Injection TA-Temp. Aban.
WI-Water Injection

Recvd. Ama

RECEIVED
CORE LABORATORIES, INC.
Petroleum Reservoir Engineering
DALLAS, TEXAS
JAN 18 1978 JAN 23 1978
January 10, 1978
MESA PETROLEUM
CENTRAL DIV.

1-19-78
1-19-78

JAN 17 1978

D.W.D.
L.W.C.
file

As per Stan,
gas analysis
comparable to
previous samples
Jcy

JLF
SD

GD
TLS

Page 1 of 1
File RFL 77867

R.V.L.K.
I.R.B.
L.W.L.
11 file


Company Mesa Petroleum Company Formation _____
Well Lisbon Fed. 2-21F County San Juan
Field Little Valley State Utah

HYDROCARBON ANALYSIS OF Meter Run GAS SAMPLE

COMPONENT	MOL PERCENT	GPM
Hydrogen Sulfide	1.49	
Carbon Dioxide	17.60	
Nitrogen	9.55	
Methane	63.57	
Ethane	5.00	1.330
Propane	1.54	0.421
iso-Butane	0.35	0.114
n-Butane	0.46	0.144
iso-Pentane	0.16	0.058
n-Pentane	0.13	0.047
Hexanes	0.08	0.033
Heptanes plus	0.07	0.032
	100.00	2.179

Calculated gas gravity (air=1.000) = 0.833
Calculated gross heating value = 822 BTU
per cubic foot of dry gas at 14.65 psia at 60°F.
Collected at 740 psig and °F., in the field.
Cylinder No. 30.

Core Laboratories, Inc.



P. L. Moses, Manager
Reservoir Fluid Analysis

PLM:HRF:gb

1cc.- Mr. James Archer
Mesa Petroleum Co.
Aztec, New Mexico 87410


4cc.- Mesa Petroleum Co.
Amarillo, Texas 79105

These analyses, opinions or interpretations are based on observations and material supplied by the client to whom, and for whose exclusive and confidential use, this report is made. The interpretations or opinions expressed represent the best judgment of Core Laboratories, Inc. (all errors and omissions excepted); but Core Laboratories, Inc. and its officers and employees, assume no responsibility and make no warranty or representations as to the productivity, proper operation or profitability of any oil, gas or other mineral well or sand in connection with which such report is used or relied upon.

LAW OFFICES OF
HUGH C. GARNER

SUITE 580 KENNECOTT BUILDING
SALT LAKE CITY, UTAH 84133

(801) 532-5660



February 13, 1978

Division of Oil, Gas, and Mining
Department of Natural Resources
State of Utah
1588 West North Temple
Salt Lake City, Utah

RE: Application for Permit to Drill, etc.
Cordillera Corporation, Applicant
Little Valley Field, San Juan County, Utah


ATTN: Mr. Cleon J. Feight

Gentlemen:

On behalf of Cordillera Corporation I hand you herewith, in quadruplicate, an Application for Permit to Drill, Deepen, or Plug Back the well designated as Well No. 1 Cordillera located in Section 16, Township 30 South, Range 25 East, S.L.M. Said well is to be drilled at the location specified under the Order issued by your Board in Cause No. 70-2.

In the interest of time, please forward directly to the applicant, Cordillera Corporation, at 2334 East Third Avenue, Denver, Colorado 80206, the approved application copies.

Very truly yours,


Hugh C. Garner

HCG:lms

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☐GAS
WELL ☒

OTHER

SINGLE
ZONE ☐

2. NAME OF OPERATOR

Cordillera Corporation

3. ADDRESS OF OPERATOR

2334 East Third Avenue, Denver, CO 80206

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

500' FSL & 500' FWL Sec 16, T30S, R25E

At proposed prod. zone

Same SW SW SW San Juan County, Utah

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

500'

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

16. NO. OF ACRES IN LEASE

640

19. PROPOSED DEPTH

9200

17. NO. OF ACRES ASSIGNED
TO THIS WELL

-

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

GR 6847'

22. APPROX. DATE WORK WILL START*

March 1, 1978

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
13 3/4	10 3/4	32.75	1000' KB	475 Sx
9 7/8	7 5/8	29.70	5155' KB	400 Sx

This well to be drilled to test for gas in the Mississippian formation. Rotary tools will be used through the above casing. In the event of commercial production a 5" liner will be run from 5155 through the production zone and cemented with 250 sx. Blowout preventor will be installed with kill lines below the blind rams and tested at regular intervals. A 6 3/4" hole will be drilled below the 7 5/8 casing with directional tools to assure the bottom of hole being directly under surface location. Salt saturated mud will be used for circulation. The well will be logged and the zone tested if necessary. Restoration will be as required.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED [Signature] TITLE President DATE February 7, 1978

(This space for Federal or State office use)

PERMIT NO. B-037-11386

APPROVAL DATE

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side

February 17, 1978

Cordillera Corporation
2334 East Third Avenue
Denver, Colorado 80206

Re: Well No. State #1 Cordillera
Sec. 16, T. 30 S, R. 25 E,
San Juan County, Utah

Gentlemen:

Insofar as this office is concerned, approval to re-enter the above referred to well is hereby granted in accordance with the Order issued in Cause No. 70-2, dated August 24, 1977. However, you shall be required to comply with the following provisions of said Order during such re-entry operation:

- 1) "Said well or hole must bottom with a vertical deviation of 75 feet or less from the surface location of said well. Also, a comprehensive directional survey, made by an independent, recognized company, must be filed with this Division as soon as possible after said well has had casing set and before completion efforts are attempted."
- 2) "After said well has been completed the staff will be immediately notified in order that an interference test, as prescribed by the Staff, might be arranged with Mesa Petroleum Corporation, operator of the gas well located in Section 22."
- 3) After the above mentioned interference test data has been submitted to, and evaluated by, the Division's staff, a hearing will be held for the purpose of pro-rating the production from the well in Section 16, if required.

Further, it is requested that Cordillera assures a drilling and plugging bond has been properly filed with the Division of State Lands prior to commencement of operations.

Should you determine that it will be necessary to plug and abandon

Cordillera Corporation
February 17, 1978
Page Two

this well, you are hereby required to immediately notify the following:

PATRICK L. DRISCOLL - Chief Petroleum Engineer
HOME: 582-7247
OFFICE: 533-5771

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling.

Further, it is requested that this Division be notified within 24 hours after commencement of operations, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-037-11356.

Very truly yours,

DIVISION OF OIL, GAS, AND MINING

CLEON B. FEIGHT
Director

SW
cc: U.S. Geological Survey
Mesa Petroleum Corporation

CORDILLERA CORPORATION

2334 EAST THIRD AVENUE

DENVER, COLORADO 80206

(303) 355-3535

19 June 1978

DIVISION OF OIL, GAS AND MINING
State of Utah
1588 West North Temple
Salt Lake City, Utah 84116

RE WELL STATUS REPORT
State #1 Cordillera
Sec 16, T30S, R25E
San Juan County, Utah

Gentlemen:

Subject well is being drilled directionally by Eastman Whipstock, Inc. Depth on the morning of June 19, 1978, was 8,864 feet, with coordinates from surface location being N 37', E 22'.


No water zones have been penetrated as yet, but had sour gas in clastics at 7,369 feet.

Have safety engineer with necessary alarms and equipment on location, also using degasser and iron sponge in drilling fluid. Mud was showing up to 200 ppm H₂S, but after degassing and treating it is nil.

Very truly yours,

Jack M. Lucey
JACK M. LUCEY

JML/nll



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR CORDILLERA CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 2334 East Third Avenue Denver, CO 80206		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 500' FWL, 500' FSL, Sec. 16, T30S, R25E		8. FARM OR LEASE NAME State
14. PERMIT NO. 43-037-11356		9. WELL NO. #1
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 6847		10. FIELD AND POOL, OR WILDCAT Little Valley
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec 16, T30S, R25E
		12. COUNTY OR PARISH San Juan
		13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) <input type="checkbox"/> Well status	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

June Activity

Drilled to 9404'. Preparing to run DST #1 from 9259' - 9404' prior to reaching gas - water contact. The coordinates at this depth from surface location S 26.8' E 14'.

Sample tops:	Lower Hermosa	8834'
	Molas	8953'
	Mississippian	8992'
	Mississippian	
	Porosity	9250'

No water flows have been encountered - all salt to Hermosa then shales, domilite and limestone.

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Engineer

DATE July 7, 1978

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

CORDILLERA CORPORATION

2334 EAST THIRD AVENUE • DENVER, COLORADO 80206 • (303) 355-3535

File

3MP

11 July 1978

DIVISION OF OIL, GAS, AND MINING
Department of Natural Resources
State of Utah
1588 West North Temple
Salt Lake City, Utah 84116

Gentlemen:

RE WELL NO. STATE #1 CORDILLERA
Section 16, T 30 S, R 25 E
San Juan County, Utah

In accordance with the order issued in Cause No. 70-2 dated August 24, 1977, we enclose a directional survey made by Eastman Whipstock Company on the captioned well. This survey is submitted as requested prior to startup of well completion efforts.

As previously reported, we topped the Mississippian at 8,992' measured depth. The record of survey does not show the coordinates at this particular depth, but by interpolation we find that the coordinates would be 10.47' North, 17.35' East of the surface location.

Please refer any questions that may arise to Mr. Jack Lucey of this office.

Very truly yours,

Nancy Lettola


NANCY LETTOLA

nll

Enclosures

PLAN

EASTMAN WHIPSTOCK, INC.




JOB NO. RM 578-00790

CORDILLERA CORP
JOB RM578-D0790
SPILLER CANYON STATE 11

DATE 5/15/78

RECORD OF SURVEY

RADIUS OF CURVATURE METHOD



Oil-Tronix Ltd.

MEASURED DEPTH FEET	DRIFT ANGLE D M	DRIFT DIRECTION D	TRUE VERTICAL DEPTH FEET	R E C T A N G U L A R C O O R D I N A T E S FEET		DOG LEG SEVERITY DEG/100FT
4796.	6 45	N 17 E	4778.98	300.74 N	198.70 E	0.0
5150.	6 45	N 23 E	5130.52	339.82 N	212.92 E	0.2
5180.	5 0	N 26 E	5160.36	342.61 N	214.20 E	5.9
5207.	5 30	N 29 E	5187.24	344.81 N	215.34 E	2.1
5238.	3 45	N 35 E	5218.14	346.93 N	216.66 E	5.8
5269.	2 30	N 63 E	5249.09	348.02 N	217.93 E	6.3
5299.	2 30	S 66 E	5279.06	348.06 N	219.19 E	7.2
5331.	3 45	S 33 E	5311.01	346.94 N	220.50 E	6.7
5373.	4 30	S 0 E	5352.90	344.08 N	221.35 E	5.8
5404.	5 30	S 4 W	5383.78	341.38 N	221.25 E	3.4
5436.	6 0	S 6 W	5415.61	338.19 N	220.97 E	1.7
5497.	7 15	S 6 W	5476.20	331.19 N	220.24 E	2.0
5529.	7 45	S 1 W	5507.93	327.02 N	219.98 E	2.6
5550.	8 45	S 2 E	5528.71	324.01 N	220.01 E	5.2
5580.	7 30	S 1 E	5558.40	319.77 N	220.12 E	4.2
5611.	6 15	S 11 W	5589.18	316.08 N	219.80 E	6.1
5637.	5 30	S 24 W	5615.04	313.55 N	219.00 E	5.9
5668.	5 30	S 40 W	5645.89	311.04 N	217.43 E	4.9
5728.	4 45	S 55 W	5705.65	307.43 N	213.49 E	2.5
5760.	4 30	S 49 W	5737.54	305.84 N	211.45 E	1.7
5789.	4 15	S 54 W	5766.46	304.46 N	209.72 E	1.6
5820.	4 15	S 58 W	5797.37	303.17 N	207.82 E	1.0
5851.	4 0	S 65 W	5828.29	302.11 N	205.86 E	1.8
5888.	5 0	S 53 W	5865.17	300.62 N	203.38 E	3.7
5949.	7 30	S 27 W	5925.80	295.58 N	199.14 E	6.1
5981.	7 30	S 29 W	5957.52	291.89 N	197.18 E	0.8
6045.	7 30	S 25 W	6020.97	284.45 N	193.39 E	0.8
6136.	7 30	S 24 W	6111.19	273.64 N	188.47 E	0.1
6228.	7 30	S 26 W	6202.40	262.75 N	183.39 E	0.3
6319.	7 45	S 31 W	6292.60	252.15 N	177.63 E	0.8

MEASURED DEPTH FEET	DRIFT ANGLE D M	DRIFT DIRECTION D	TRUE VERTICAL DEPTH FEET	R E C T A N G U L A R C O O R D I N A T E S FEET		DOG LEG SEVERITY DEG/100FT
6412.	8 15	S 27 W	6384.69	240.83 N	171.36 E	0.8
6506.	8 45	S 26 W	6477.66	228.40 N	165.16 E	0.6
6599.	8 45	S 29 W	6569.57	215.85 N	158.63 E	0.5
6690.	9 30	S 25 W	6659.41	203.00 N	152.08 E	1.1
6741.	9 45	S 27 W	6709.70	195.33 N	148.34 E	0.8
6802.	10 15	S 28 W	6769.77	185.93 N	143.45 E	0.9
6833.	10 0	S 28 W	6800.28	181.13 N	140.89 E	0.8
6895.	10 0	S 26 W	6861.34	171.53 N	136.01 E	0.6
6913.	10 0	S 31 W	6879.06	168.79 N	134.51 E	4.8
6943.	9 15	S 34 W	6908.63	164.56 N	131.82 E	3.0
6972.	7 30	S 47 W	6937.32	161.35 N	129.08 E	8.9
7016.	6 0	S 68 W	6981.01	158.59 N	124.75 E	6.5
7047.	5 0	S 59 W	7011.87	157.26 N	122.09 E	4.3
7078.	5 15	S 57 W	7042.74	155.80 N	119.74 E	1.0
7140.	5 15	S 59 W	7104.48	152.79 N	114.93 E	0.3
7202.	5 15	S 60 W	7166.22	149.91 N	110.04 E	0.1
7265.	5 0	S 61 W	7228.96	147.14 N	105.14 E	0.4
7325.	5 0	S 63 W	7288.73	144.68 N	100.52 E	0.3
7385.	5 30	S 57 W	7348.48	141.94 N	95.76 E	1.02
7478.	6 0	S 59 W	7441.01	137.00 N	87.86 E	0.6
7572.	5 45	S 59 W	7534.52	132.04 N	79.61 E	0.3
7663.	5 30	S 59 W	7625.07	127.45 N	71.97 E	0.3
7756.	5 30	S 57 W	7717.64	122.73 N	64.41 E	0.2
7880.	5 30	S 59 W	7841.07	116.43 N	54.33 E	0.2
8065.	5 30	S 62 W	8025.21	107.70 N	38.90 E	0.2
8107.	5 30	S 62 W	8067.02	105.81 N	35.35 E	0.0
8138.	5 30	S 36 W	8097.88	103.88 N	33.13 E	8.0
8189.	5 30	S 14 W	8148.64	99.47 N	31.07 E	4.1
8249.	5 45	S 9 W	8208.34	93.72 N	29.90 E	0.9
8342.	6 0	S 8 W	8300.86	84.30 N	28.49 E	0.3

MEASURED DEPTH FEET	DRIFT ANGLE D M	DRIFT DIRECTION D	TRUE VERTICAL DEPTH FEET	R E C T A N G U L A R C O O R D I N A T E S FEET		DOG LEG SEVERITY DEG/100FT
8433.	6 0	S 7 W	8391.36	74.87 N	27.25 E	0.1
8527.	6 30	S 10 W	8484.80	64.75 N	25.74 E	0.6
8619.	7 0	S 12 W	8576.16	54.13 N	23.68 E	0.6
8772.	6 30	S 7 W	8728.09	36.40 N	20.71 E	0.5
8858.	7 0	S 7 W	8813.49	26.37 N	19.48 E	0.6
8959.	6 45	S 8 W	8913.76	14.38 N	17.90 E	0.3
9050.	7 0	S 8 W	9004.11	3.59 N	16.38 E	0.3
9166.	5 45	S 8 W	9119.38	9.16 S	14.59 E	1.1
9258.	5 30	S 2 W	9210.94	18.13 S	13.81 E	0.7
9352.	6 0	S 11 W	9304.46	27.48 S	12.74 E	1.1
9482.	5 45	S 25 W	9433.78	40.11 S	8.64 E	1.1

FINAL CLOSURE - DIRECTION:
DISTANCE:

S 12 DEGS 9 MINS 10 SECS E
41.03 FEET

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING
1588 West North Temple
Salt Lake City, Utah 84116

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well Name & Number: CORDILLERA STATE #1

Operator: Cordillera Corporation Address: 2334 East Third Ave. Denver, CO
Drawer 2800 80206

Contractor: Cactus Drilling Corp. Address: Midland, TX 79701

Location SW 1/4 SW 1/4; Sec. 16 T. 30 N. R. 25 E.; San Juan County.
S N

Water Sands:

None encountered.

Depth:

Volume:

Quality:

From-

To-

Flow Rate or Head

Fresh or Salty

1. _____
2. _____
3. _____
4. _____
5. _____

(Continue on Reverse Side if Necessary)

<u>Formation Tops:</u>	Lower Hermosa	8834'
	Molas	8953'
	Mississippian	8992'

Remarks: The tops are measured depths and not true vertical depths.

- NOTE:
- (a) Upon diminishing supply of forms, please inform this office.
 - (b) Report on this form as provided for in Rule C-20, General Rules and Regulations and Rules of Practice and Procedure.
 - (c) If a water analysis has been made of the above reported zone, please forward a copy along with this form.

CORDILLERA CORPORATION

2334 EAST THIRD AVENUE • DENVER, COLORADO 80206 • (303) 355-3535

July 21, 1978

Division of Oil, Gas and Mining
Department of Natural Resources
State of Utah
1588 West North Temple
Salt Lake City, Utah 84116


Re: Cordillera State #1
Section 16, T30S, R25E
San Juan County, Utah

Gentlemen:

On July 11, 1978 we sent you a copy of Eastman's directional survey on the subject well. The report did not include the plan view, as it was not complete at the time of mailing.

Enclosed is the plan view for inserting in the survey report.

Very truly yours,


Jack M. Lucey

JML/rs
Encl.

CORDILLERA CORPORATION

2334 EAST THIRD AVENUE

DENVER, COLORADO 80206

(303) 355-3535

July 28, 1978

LP

Division of Oil, Gas & Mining
Department of Natural Resources
State of Utah
1588 West North Temple
Salt Lake City, Utah 84116

Re: Cordillera State #1
Little Valley Field
San Juan County, Utah

Attn: Mr. Patrick L. Driscoll
Chief Petroleum Engineer

Gentlemen:

Although we are not through completing the subject well enclosed is the information we have to date, the DST and geological report. Copies of the logs are being sent direct by Schlumberger Well Services. We did perforate 104' of porosity, followed with an acid job and are in the process of cleaning up for a test.

As mentioned over the phone, we had furnished all information to date to Mesa Petroleum prior to Mr. Lemmon's letter to you.

Very truly yours,

Jack M. Lucey

JML/rs

Encl.

LIONEL BRENNEMAN - PETROLEUM GEOLOGIST

630 GUARANTY BANK BUILDING
DENVER, COLORADO 80202
OFFICE 303 / 534-6188
HOME 303 / 794-7092

LITTLE VALLEY PROSPECT

WELL REPORT

CORDILLERA CORP.

NO. 1 SPILLER CANYON

SWSW Section 16-30S-25E

San Juan County, Utah

TABLE OF CONTENTS

Resume.	2
Formation Tops.	4
Bit Record.	4
Deviation Surveys	4
Mud Properties.	5
Sample Descriptions	6
Drillstem Tests10
Discussion.11
Sample and Drilling Time Chart - Packet in Back	
Log Analysis.12

630 GUARANTY BANK BUILDING
DENVER, COLORADO 80202
OFFICE 303 / 534-6188
HOME 303 / 794-7092

RESUME

Operator: Cordillera Corp. 2334 East 3rd Avenue
Denver, Colo. 80206

Well: No. 1 Spiller Canyon - State

Location: SWSW Section 16 - 30S - 25E San Juan County,
Utah

Field: Little Valley

Elevation: 6847 ground, 6861 Kelley Bushing

Casing: 7 5/8" to 5155", 10 3/4" @ 1000', 4 1/2",
N80, 11.6# @ 9517

Hole Size: 6 3/4" to 9116, 6 1/2" to 9517

Total Depth: 9510 driller, 9517 logs

Bottom Formation: Mississippian - Leadville

Mud: Salt Saturated Gel

Spud: 5/22/70

Completed: Ran Production Casing 7-4-78

Cores: None

DST's: No. 1 9259-9404

Logs: Dual Lateralog 9155-9517, Compensated Neutron-
Formation Density 7520-9517, Borehole Compensat-
ed Sonic-GR-Caliper 7200-9517

Contractor: Cactus Drilling Co, Rig 20

Status: Gas Well - Hydrocarbon Gas w/2000 PPM H₂S in
Mississippian-Leadville Formation.

FORMATION TOPS - ELEV. KB 6861

	<u>Samples</u>	<u>Logs</u>	<u>Comparison With Mesa 2-21-F Federal</u>
Lower Hermosa	8834	8833 (-1972)	+144
Molos	8960	8956 (-2095)	+ 94
Mississippian	8890	8993 (-2132)	+113
Dolomite	9240	9243 (-2382)	+ 56
Total Depth	9510	9517 (-2656)	

BIT RECORD

6 3/4" Hole

<u>No.</u>	<u>Make</u>	<u>Type</u>	<u>Depth Out</u>	<u>Footage</u>	<u>Hours</u>
1	Security	M4N	5200	Used for clean out	
2	Smith	F-2	5290	90	11 1/2
3	Security	S88	5548	258	29 3/4
4	Smith	F-2 r.r.	5658	110	25 1/2
5	Smith	F-2	5871	213	13 1/2
6	Security	S88 r.r.	5955	84	23 3/4
7	Smith	F-2 r.r.	5986	31	19
8	Security	M4N r.r.	6016	30	8 1/2
9	Smith	F-2	6927	911	78 3/4
10	Smith	V2HJ	7030	103	3 1/2
11	Smith	V2HJ	7367	337	20 3/4
12	Smith	V2HJ	7614	247	20 3/4
13	Smith	V2HJ	8107	493	23 1/2
14	Smith	V2HJ	8181	74	5 1/2
15	Smith	V2HJ	8746	565	24 1/4
16	Smith	F-2	8894	148	36 1/2
17	Smith	V2HJ	8926	32	21
18	Security	S88	9116	190	81
		Changed hole size to 6 1/2"			
19	Hughes	J-44	9404	288	85 1/2
20	Hughes	J-33	9510	106	24

DEVIATION SURVEYS

This was a directionally drilled hole and survey control run by Eastman Survey. Detailed certified report has been prepared by them.

MUD PROPERTIES

Northern Drilling Fluids - Everette Toombs, Engineer
(Saturated Salt Gel) w/1-2% Oil from 6400 to T.D.

Date	Depth	Wt.	Vis.	Ph	Water Loss	Cake	Solids %	Total Salt (PPM)
5/22	5240	10.4	33	11	22	3/32	12½	301,950
5/23	5290	10.4	34	11.5	10	2/32	12½	311,850
5/24	5365	10.4	36	11	12.8	2/32	12½	336,700
5/25	5513	10.5	33	11	14.3	2/32	13	313,500
5/26	5602	10.4	31	11	14.8	2/32	13	313,500
5/27	5660	10.5	34	11.5	9.8	2/32	13	326,700
5/28	5871	10.4	37	11.5	14.8	2/32	12½	326,700
5/29	5931	10.5	36	11.5	11.8	3/32	13	305,250
5/30	5958	10.4	33	10	20	3/32	13	305,250
5/31	6016	10.4	37	11.5	13.8	2/32	13	317,000
6/2	6122	10.4	35	11.5	13.6	2/32	13½	326,700
6/3	6400	10.4	35	11.5	19.8	2/32	12½	310,200
6/4	6677	10.4	38	12	10.4	2/32	12½	313,500
6/5	6785	10.2	37	11.5	16.3	2/32	12	297,000
6/7	6935	10.3	38	12	16	2/32	12	300,300
6/9	7102	10.4	38	12	11.2	2/32	12	300,300
6/10	7376	10.4	37	12	10.8	2/32	12	300,300
6/11	7375	10.6	37	9	4.2	2/32	14½	265,650
6/12	7567	10.8	37	11.5	5.2	1/32	16	297,000
6/13	7706	11.1	38	12.5	26.4	3/32	17	315,750
6/14	8103	11.1	46	12	8.2	3/32	17½	330,000
6/15	8150	11.3	45	10.5	17.3	3/32	18½	317,800
6/16	8276	11.4	45	11	45.1	2/32	18½	330,000
6/16	8490	11.3	42	10.5	?	2/32	18½	326,100
6/17	8700	11.5	44	11.5	?	3/32	19½	313,500
6/18	8790	11.6	72	10.5	9.7	2/32	19	297,000
6/19	8864	11.3	55	11	9	2/32	18	297,000
6/20	8897	12	74	11	13	2/32	20	310,200
6/21	8918	11.5	45	12.5	17.8	2/32	18½	321,750
6/22	8932	11.3	58	12	8.4	2/32	16½	297,000
6/23	8964	11.3	54	12	7.0	2	18	303,600
6/24	9030	10.8	40	11	12.1	2	16	316,800
6/25	9090	11.1	45	12	11.2	2	17½	305,250
6/26	9130	11	40	12.5	7.1	2	17	330,000
6/27	9192	10.9	54	12	5.1	2	16½	297,000
6/28	9256	11	45	12	5.2	2	17½	306,900
6/29	9357	11	45	12	4.6	2	17½	297,000
6/29	9400	11.1	47	12.5	4.2	2	18	306,900
6/30	9404	11.1	50	12.5	4.2	2	18	306,900
7/2	9468	10.8	38	11	7.0	2	16	330,000
7/3	9510	11	42	12.5	6.1	2	17½	297,000

- 8830-40 Ls, wh- lt. gray, soft gummy - fn. x ln. & soft, clean to (Lower argill, with gry. soft shale laminae. 80%
Hermosa) Sh, med. gry.-tan, med. hd, v. calc. to fn. x ln. buff Ls.
blky. to platy 20%. Trc. salt.
- 8840-50 Sh, med. gry,-tan and buff, med. hd. - soft, blocky to platy
v. calc, few chalky ls. lam., Trc. Ls. Sab.
- 8850-60 Sh, Sab
- 8860-70 Sh, Sab, inc. in Ls, soft gummy as above
- 8870-80 Sh, sab 90%
Sh, sab 10%
- 8880-90 Sh, med. gry-tan, soft, blocky, v. calc, w/Ls. inclusions 60%
Ls, sab 40%
- 8890-8900 Sh, med. gry, hard dense, platy, vs. calc, few calcite filled
fractures. Trc. Ls, tan, hd. dense, argill. lam., blocky.
- 8900-10 Sh, med. gry, soft, fiss-blocky, sli. calc, trc. coal, blk,
soft, blocky. Trc. Ls, tan, hd, dense, argill.
- 8910-20 Ls, Lt. gry, soft, chalky - v. argill., becomes gummy when
wet. Ls, med. gry, hd, dense to fn. xln, argill. Trc. Sh
sab. Trc. Ls, brn, fn xln, friable, gd. per, sli. stain.
- 8920-30 Sh, med. gry, soft, platy, v. calc, Trc. pyrite, Trc. Ls,
wh, soft, chalky, argill. Trc. Ls, brn, hd, dense.
- 8930-40 Sh, sab, Trc. pyrite, Trc. Ls, Sab.
- 8940-50 Ls, Lt, gry - med. gry, hd, dense to fn. xln, no por or perm
sli, argill. Few calcite filled fractures, some brn. sil.
stain. Trc. Sh, sab.
- 8950-60 Ls, Lt. gry-tan, dense-fn. x ln, hd, w/trc. dk Ls inclusion,
low - 5% xln. por. trc. stain. Trc. Ls, lt. gry, soft, gummy,
argill., Trc. Sh, sab.
- 8960-70 Sh, grn. gry, soft, blocky, non-calc., 50% Ls, tan-brn-med gry,
(Molose) hard, dense to trc. pinpoint por. w/oil stain, Trc. Ls, wh-
lt. gry, soft, gummy, argill.
- 8970-80 Sh sab, Ls sab
- 8980-90 Sh, sab, Ls sab
- 8990-9000 Ls, dk. brn - med. gry, v. hd, dense, dolomitic to Ls, Lt. gry,
hard, fn-med. xlr. some vein calcite. Trc. Sh, grn, gry, soft
blocky.

- 9000-10 Ls, Lt. gry-tan, hd, dense, to fn. xln, sli. argill, Ls med. gry-dk. brn hd, dense to v. fn. xln, trc. pinpoint por Ls., buff, hd., fn. xln. Sh, grn. gry, soft, blocky 10%. Trc. Sh, blk, carb.
- 9010-20 Ls, wh- lt. gry to trc. buff, med. hd-soft, fn. xln, low inter. xln por, trc. Ls, med. gry sab. Trc. Sh sab.
- 9020-30 Ls, lt. gry - lt. grn. gry, hd.-med. soft, fn. xln. to dense, pyritic, 80%. Sh, grn. gry, soft, blocky 20%
- 9030-40 Ls, sab, 80% Sh, sab 20% Trc. pyrite
- 9040-50 Ls, Lt. gry-grn. gry - buff, hd., dense - fn. xln, argill, trc. pinpoint vugular porosity w/oil stain. 90%. Sh, sab 10%
- 9050-55 Ls, wh - lt. gry to mottled lt. gry & med. gry, med. hd.-soft dense to fn. xln, some gummy, no p-p. Anhyd buff, soft, dense, rdd pellets.
- 9055-60 Ls, lt. gry-wh, fn. xln - dense, hd, tite several pieces of pellet & lump Ls, well cemented w/trc. dead oil stain.
- 9060-70 Ls, lt. gry - wh, sab w/Ls. med. gry, fn. xln, hd, dense, argill w/Ls, lt. gry, coarse grn. lumps. Trc. Sh. grn. gry, blocky, soft, sli. calc.
- 9070-80 Ls, med. gry, hd, dense, fossiliforens, v. argill, w/Ls. sab.
- 9080-90 Poor sample
- 9090-9100 Ls, md. gry, hd, dense - fn. xln, pinpoint vugular porosity trace crinoid sten, sli. argill. Trc. sh, blk, carb. Trc. Ls, dk. gry, lump - pelletal, dense.
- 9100-10 Ls, wh, soft, chalky to Ls, lt. gry, hd, fn. xln, no p-p.
- 9110-20 Ls, lt. gry. tan, hd, dense - fn. xln, streaks blk. argill. material. Trc. Sh., black, hd, fissile.
- 9120-30 Ls, sab, Trc. Sh. black sab, Trc. pyrite
- 9130-40 Ls, Lt. gry, hd, dense - fn. xln, few streaks med. gry. argill. material. Ls, wh, soft, chalky, no evidence of fossil debris. No porosity.
- 9140-50 Ls, wh, soft, chalky, disintegrates when wet. 80% Ls, lt. gry. hd, dense as above 20%. No porosity.
- 9150-60 Ls, wh, soft, chalky w/med. gry. argill. streaks 50% Ls lt. gry, hd, dense - fn. xln, few fractures with calcite fill. No porosity.
- 9160-70 Ls, Lt. gry - Lt. grn. gry, hd, fn. xln, sli. argill, few calcite filled fractures, no p-p. Ls, wh, soft, chalky.

- 9170-80 Ls, lt. gry, hd, dense - fn. xln, trc. pellet inclusion, trc. blk. argill. inclusion. 80%. Ls, wh. - lt. gry. - pink, soft, chalky few argill. inclusion. 20%. No p-p.
- 9180-90 Ls, lt. gry, lt. grn. gry. hd. fn. xln, occasional pellet inclusion 50%.
Ls, wh-pink, soft, gummy, sli. argill. sab 50%. No p-p.
- 9190-9200 Ls, wh-lt. gry, soft, chalky, argill. streaks, dk. gry.
- 9200-10 Ls, wh-lt. grn. gry.-pink, soft, fine interbeds of dk. gry. argill. material 90% trc. Sh., blk, calc. fissile.
Ls, lt. gry, hd, fn. xln, no p-p. 10%.
- 9210-20 Ls, lt. gry, soft, mottled w/dk. gry, argill material. trc. Sh, dk. gry, soft, blocky, calc.
- 9220-30 Ls, wh-pink, soft, sli. argill, chalky w/ some Ls, lt. grn. gry., hd, fn. xln. Trc. Sh, blk, fiss. blocky.
- 9230-40 Sh, med. gry, hd. fiss, v. calc., in part mottled with wh. calc. material.
Ls, Lt. gry-grn. gry, hd, dense-fn xln. No p-p.
- 9240-50 Dolomite, lt. gry, v. hd, v. fn. xln, tite, few argill. streaks, no p-p.
- 9250-60 Dolomite, sab, increase in argill material 80% low p-p.
Ls, wh-pink, soft, argill.
- 9260-70 Dolomite, lt. gry - med., v. hd., fn-md. xln, v. argill. Trc. Ls, lt. gry, soft, chalky.
- 9270-80 Dolomite, sab, Trc. Sh, med. gry, hd. blocky, v. calc.
- 9280-90 Ls, lt. grn. gry, hd, dense - fn. xln, Trc. Dolo, med. gry, hd. dense - fn. xln, low p-p. Trc. Ls, wh-lt. gry, soft, chalky, v. argill.
- 9290-9300 Ls, wh-med. gry. mottled, hd-soft, v. argill, pinpoint vugular porosity.
Dolo, med. gry, hd., fn. xln, pinpoint vugular porosity some with calcite fill, sli. oil stain in vugs.
- 9300-10 Dolo, lt. gry, hd. fn. xln, clean, low p-p, trc. Ls, sab.
- 9310-20 Ls, wh-lt. gry, soft, argill., chalky - fn. xln.
- 9320-30 Ls, sab
- 9330-40 Ls, lt. gry - lt. grn. gry, hd, fn. xln, few argill inclusions fractured w/ v. light stn. on fractures, low porosity. Trc. Ls, wh-pink, soft, chalky.
- 9340-50 Dolo, med. gry, med. hard, fn. xln, friable, gd. por est. 12 percent, lt. oil stain, trc. Dolo, med. gry, hd. dense fractured.
- 9350-60 Dolo, med. gry. with some lt. gry, v. hd, fn. xln. - dense,

argill, trc. pinpoint vugular porosity w/light oil stain,
inter xln, porosity est. 6-8 percent.

- 9360-70 Dolo, sab
- 9370-80 Dolo, sab
- 9380-90 Dolo, sab 50%, Ls, lt. gry, soft, mottled w/med. gry, argill material.
- 9390-9400 Dolo, sab
- 9400-10 Dolo, sab
- 9410-20 Dolo, med. gry - gry, brn, hd, fn. xln, fair por, trc. pinpoint vugular porosity, est. 12% porosity, lt. oil stain, Trc. Ls. lt. gray, fn. xln, pelletal, tight.
- 9420-30 Dolo, lt. gry - some med. gry, hd, dense - fn. xln, low porosity. 70%, Ls, lt. gry, fn. xln, hd. dolomitic, tight, 30%
- 9430-40 Dolo-Ls, lt. gry, hd. fn. xln, tight w/trc. pinpoint vugular porosity, sli. oil stain in vugular pores. 50-50 Ls. & Dolo.
- 9440-50 Dolo, lt. gry w/some med. gry, hd., fn. xln, low porosity w/Trc. pinpoint vugular porosity.
- * 9450-60 Dolo, sab 90% w/Sh, blue, soft, blocky, sli. calc. 10%
- 9460-70 Ls, lt. gry, hd, dense, fn. xln, sli. dolo, non. foss., sli. argill., 90% Sh, blue, soft, black, calc.
- 9470-80 Ls, lt. gry, hd., fn.xln, clean - sli. argill, low porosity to some pinpoint vugular porosity. Black dead oil stain.
- 9480-90 Ls, sab with abundant black dead oil stain with Ls, pink, soft, fn. xln. Trc. Sh, blk, hd. blocky, sli calc.
- 9490-9500 Ls, lt. grn. gry, hd. fn. xln, clean, black dead oil stain 70% Ls, pink, soft, fn. xln. 30%.
- 9500-10 Ls, lt. grn. gry, sab, with abundant black dead oil stain 60% Ls, pink, sab 40%

DISCUSSION

The Cordillera No. 1 Spiller Canyon was a reentry into the Pure Oil No. 1 Spiller Canyon test which was completed as a dry hole in April 1962. The original Pure test was intended to be a field development well to further evaluate the gas accumulation discovered in November 1961 by the Pubco (Mesa) 2-21-F Federal well located in the Northwest Quarter of Section 21-T30S-R25E.

During the drilling of the Pure test, the hole was permitted to deviate over 700 feet northeast of the surface location which resulted in the hole penetrating a 230' reverse fault in the Lower Hermosa formation. The additional section forced the Leadville porosity into a low structural position and the porosity was water bearing with slight gas shows.

Cordillera obtained permission from the State of Utah to reenter the Pure hole with the intention of directionally drilling the lower portion of the hole so that the location at total depth would be close to the surface location. Available data indicated the new hole would be south of the fault penetrated in the original hole and would encounter the Leadville gas bearing section at a structurally high position relative to the Pubco (Mesa) well.

The Leadville formation was encountered structurally as anticipated and the entire porous section is gas bearing. (See DST No. 1).

The Sonic and Compensated Neutron logs measured porosities ranging from 8 to 11 percent with approximately 92 feet of net effective pay.

Casing has been run, and the well is currently ready for completion.

Lionel Brenneman

DRILLSTEM TESTS

Engineer - Cliff Richards - Johnston Testers
Vernal, Utah

DST No. 1 9259-9404 (143')

Times: Initial Open 30", Initial Shutin 30"
 Final Open 60", Final Shutin 120"

	<u>Top Chart</u>	<u>Bottom Chart</u>
Pressures:		
@ 9264'		
Initial Hydrostatic:	5398	
Final Hydrostatic:	5398	
Initial Open:	869-933	
Initial Shutin:	2782	
Final Open:	971-1060	
Final Shutin:	2782	

MFE Chamber: Recovered 4.5 cu. gas @ 1000 PSI
 175 cc fluid. chlorides 200,000.
 Rw. .08, Fil. Rw. .05 @ 70°

Temperature: 148° F.

Pipe Recovery: Reversed out due to high concentration of H₂S gas.
 Measured greater than 2000 ppm H₂S.

Remarks: Gas to surface 47 minutes, 1½" blow in 5 gal. bucket
 increase to bottom in 5 minutes, increase to 28# in 10
 minutes. 2nd flow reopen @ 28# immediately, decrease
 to 8# produced water cushion and then increased to 60#
 - 480 mcf/gpd held steady.

LOG ANALYSIS
Sonic - Compensated Neutron Cross Plot

Cordillera Corporation
#1 Spiller Canyon State
SWSW Section 16-30S-25E
San Juan County, Utah
Little Valley Field

Page 1 of 3

Depth (Sonic)	Sonic Travel Time	Porosity CNL	Lithology	Gas Effect	Rw	Rt	% Porosity	% Water Saturation	Remarks
8994 - 9013	48	6 - 8	Dol		0.067	1000	3	27	
9034 - 48	50	2 1/2 - 3	Lm			400/1000	2	--	
9048 - 52	60	7	Lm	*		500	8 1/2	14	Gas
9052 - 68	48	0	Lm			----	0		
9068 - 71	51	7	Lmy Dol			50	3 1/2	--	Gas
9071 - 85	48	0	Lm			----	0	--	
9085 - 90	51	8 1/2	Lmy Dol			150	4	53	
9090 - 98	56	17	Dol	*		120	9	26	* Gas
9098 - 9104	50	6 1/2	Lmy Dol			200	3	61	
9104 - 9243	48	1/2	Lm			1000 +	0 - 1/2	--	
9243 - 53	50	4 1/2	Dol Lm			800	2 1/2	--	
9253 - 58	55	13	Dol	*		700	7	14	Gas

LOG ANALYSIS
Sonic - Compensated Neutron Cross Plot

Cordillera Corporation
#1 Spiller Canyon State
SWSW Section 16-30S-25E
San Juan County, Utah
Little Valley Field

Page 2 of 3


Depth (Sonic)	Sonic Travel Time	Porosity CNL	Lithology	Gas Effect	Rw	Rt	% Porosity	% Water Saturation	Remarks
9258 - 64	47 1/2	3	Lm & Dol		0.067	---	1	--	
9264 - 84	52 1/2	7 1/2	Lmy Dol	*		750/1000	5	18	Gas
9284 - 94	55	8 - 12	Lmy Dol			1000/800	5 - 8 1/2	11	Gas
9294 - 9305	51	1	Anhy & Lm			1000 +	1	--	
9305 - 14	51 1/2	4 1/2	Lm	*		700	3	33	Gas
9314 - 22	52 1/2	7 1/2	Dol Lm	*		700	4 1/2	22	Gas
9322 - 30	50	3 1/2	Dol Lm			1000	2	--	
9330 - 40	48	1/2	Lm			----	0	--	
9340 - 50	48 1/2	4	Lm & Dol			1000	2	--	
9350 - 60	49	5 1/2	Lmy Dol			700	2 1/2	--	
9360 - 72	52	10	Dol	*		200	5	37	Gas
9372 - 80	47	2 1/2	Dol & Lm			1000/2000	1/2	--	

LOG ANALYSIS
Sonic - Compensated Neutron Cross Plot

Cordillera Corporation
#1 Spiller Canyon State
SWSW Section 16-30S-25E
San Juan County, Utah
Little Valley Field

Page 3 of 3

Depth (Sonic)	Sonic Travel Time	Porosity CNL	Lithology	Gas Effect	Rw	Rt	% Porosity	% Water Saturation	Remarks
9330 - 83	52	10	Dol	*	0.067	800	5	18	Gas
9383 - 89	47	4	Lm & Dol			2000	1	--	
9339 - 94	52 1/2	12 1/2	Dol	*		700	6	16	Gas
9394 - 9403	48	4 1/2	Dol Lm			2000	2		
9403 - 15	51	11 1/2	Dol	*		1100	5	16	Gas
9415 - 21	49	9	Dol	*		2000	3 1/2	17	Gas
9421 - 46	46 1/2	3 1/2	Lmy Dol			2000	1		
9446 - 49	50	6	Dol & Lm			180	3	64	Probable Water
9449 - 75	48	1/2	Lm			2000+	0	--	
9475 - 82	51 1/2	6	Dol Lm			350	3 1/2	40	Probable Water
9482 - 94	48	2 1/2	Lm			1000	1	--	



PRESSURE LOG*


Field Report No. 09725 D

Instrument:
Number J-303

Capacity 6700 p.s.i.

Depth 9269 ft.

*a continuous tracing of the original chart



5398.5#
FINAL HYDROSTATIC

FINAL SHUT IN


2782.9#

1 HOUR
←

W
SW

1500

1900



JOHNSTON

Schlumberger

computerized
data
analysis

COMPUTERIZED DATA ANALYSIS

JULY 10, 1978

GENTLEMEN:

THE ENCLOSED TEST APPEARS TO BE A GOOD MECHANICAL DRILL STEM TEST DURING WHICH THE TOOLS DID FUNCTION PROPERLY. THE FORMATION PRODUCED ENOUGH RESERVOIR FLUID FOR PROPER IDENTIFICATION. RESERVOIR PRESSURE DRAWDOWN WAS SUFFICIENT AND ADEQUATE SHUT-IN BUILD-UPS DID OCCUR FOR RELIABLE QUANTITATIVE ANALYSIS. RESERVOIR PARAMETERS WERE CALCULATED BY THE HORNER METHOD.

1. FLOW RATE: AN ESTIMATED FLOW RATE OF 400 MCF/DAY OF GAS WAS NOTED DURING THIS TEST.
2. RESERVOIR PRESSURE: EXTRAPOLATION OF THE INITIAL AND FINAL SHUT-IN PRESSURE BUILD-UPS INDICATES A MAXIMUM RESERVOIR PRESSURE OF 2806 P.S.I.G. AT RECORDER DEPTH.
3. PERMEABILITY: THE CALCULATED TRANSMISSIBILITY FACTOR OF 1953 MD.-FT./CP. INDICATES AN AVERAGE EFFECTIVE PERMEABILITY TO GAS OF 0.22 MD. FOR THE REPORTED 145 FOOT TEST INTERVAL. THE CALCULATIONS WERE BASED ON A SLOPE OF 47 P.S.I./LOG CYCLE OBTAINED FROM THE FINAL SHUT-IN BUILD-UP PLOT. IT WAS ASSUMED FOR THESE CALCULATIONS: (A) GAS GRAVITY 0.70 (B) VISCOSITY 0.016 CP. (C) AND GAS DEVIATION FACTOR 0.90. THESE FIGURES WERE OBTAINED FROM THE AVAILABLE TECHNICAL LITERATURE.
4. WELL BORE DAMAGE: THE CALCULATED DAMAGE RATIO OF 10.33 INDICATES THAT MAJOR WELL BORE DAMAGE IS PRESENT AT THE TIME AND CONDITIONS OF THIS TEST. THIS VALUE INFERS THAT THE RATE OF PRODUCTION OBSERVED AT THE FORMATION FACE DURING THIS TEST MAY BE INCREASED 10.33 TIMES IF THE WELL BORE DAMAGE ALONE WERE REMOVED.
5. RADIUS OF INVESTIGATION: THE CALCULATED RADIUS OF INVESTIGATION OF THIS TEST IS 22 FEET BASED ON AN ASSUMED POROSITY OF 8%, COMPRESSIBILITY OF 5.5×10^{-4} , AND OTHER ASSUMPTIONS MADE IN NUMBER 3 ABOVE.
6. GENERAL COMMENTS: THE FORMATION EXHIBITS THE CHARACTERISTICS OF RELATIVELY LOW PERMEABILITY EFFECTIVE TO THE RESERVOIR FLUID AND INDICATES THE PRESENCE OF WELL BORE DAMAGE. AN ANOMALY WAS NOTED AT A DISTANCE OF 8 FEET FROM THE WELL BORE. WITH THE 2 TO 1 RATIO OF SLOPES, IT IS BELIEVED TO BE CAUSED BY A FAULT.

Kent Arceneaux
KENT ARCENEAUX
RESERVOIR EVALUATION
DEPARTMENT

CORDILLERA CORPORATION
SPILLER CANYON #1; SAN JUAN COUNTY, UTAH
TEST #1; 9259' TO 9404'
LOCATION SEC. 16 - T30S - R25E

F.R.# 09725 D

In making any interpretation, our employees will give Customer the benefit of their best judgment as to the correct interpretation. Nevertheless, since all interpretations are opinions based on inferences from electrical, mechanical or other measurements, we cannot, and do not guarantee the accuracy or correctness of any interpretations, and we shall not be liable or responsible, except in the case of gross or wilful negligence on our part, for any loss, costs, damages or expenses incurred or sustained by Customer resulting from any interpretation made by any of our agents or employees.

Gas Reservoir Engineering Data



JOHNSTON

Instrument No. J-303

Field Report No. 09725-D

Damage Ratio	DR	10.33	Effective Transmissibility	$\frac{Kh}{\mu}$	1953	$\frac{Md-ft.}{Cp.}$
Maximum Reservoir Pressure	P_o	2806 P.S.I.G.	Flow Rate	Q_g	400	MCF/day
INITIAL SHUT-IN			ESTIMATED			
Slope of Shut-in Curve	M_{g1}	47 PSI/log cycle	Flow Rate	Q	-	
FINAL SHUT-IN						
Potentiometric Surface	PS	4066 ft.	Pressure Gradient		0.303	PSI/ft.
(Datum Plane, Sea Level)						
Radius of Investigation		22 ft.	K (Effective to GAS)		0.22	Md.

$$\text{SLOPE } M_{G1} = 2788 - 2741 = 47$$

$$\text{SLOPE } M_{G2} = 2806 - 2701 = 96$$

Assumptions made for Calculations for Gas Recoveries

1. Q_g is taken as steady state flow and unless stated otherwise at standard conditions 14.7 P.S.I. and 60°F.
2. P_f is final formation flowing pressure at steady state flow.
3. Formation flow is taken as single phase flow. If liquid (condensate) is produced at surface, condensation is assumed to have occurred in drill pipe.
4. Radial flow is assumed.
5. Unless given, gas specific gravity is assumed to be 0.7 (air 1.0) and having pseudo critical temperature at 385° Rankin and pseudo critical pressure of 666 P.S.I.A.
6. Other standard radial flow, steady state assumptions.

Empirical Equations:

$$1. \text{ EDR} = \frac{P_o^2 - P_f^2}{M_g(\log T + 2.65)} \text{ where } M_g = \frac{P_i^2 - P_{i0}^2}{\text{Log Cycle}}$$

$$2. \text{ Transmissibility } \frac{Kh}{\mu Z} = \frac{1637^\circ T_f Q_g}{M_g}$$

$$3. \text{ P.S.} = [P_o \times 2.309 \text{ ft./PSI}] - [\text{Recorder depth to sea level.}]$$

$$4. \text{ Radius of Investigation, } r_i = \sqrt{\frac{Kt}{40\phi(1 - S_w)\mu c}} \text{ where } t = \text{time in days}$$

In making any interpretation, our employees will give Customer the benefit of their best judgment as to the correct interpretation. Nevertheless, since all interpretations are opinions based on inferences from electrical, mechanical or other measurements, we cannot, and do not, guarantee the accuracy or correctness or any interpretations, and we shall not be liable or responsible, except in the case of gross or wilful negligence on our part, for any loss, costs, damages or expenses incurred or sustained by Customer resulting from any interpretation made by any of our agents or employees.

3000

ISI

FR NO: 9725

2800

2600

2700


2600

2500

PRESSURE (P.S.I.G.)

1.0

0.5

LOG OF $\frac{T + \Delta T}{\Delta T}$ COMPUTERIZED
PLOT

2800 FSI
FR NO: 9725

2700

2600

2500

2400

2300

PRESSURE (PSI LOG)

2.0

1.0

LOG OF $\frac{T + \Delta T}{\Delta T}$ 

0

EQUIPMENT & HOLE DATA

EQUIPMENT & HOLE DATA			
Type Test	M.F.E. OPEN HOLE		
Formation Tested	MISSISSIPPI		
Elevation	6847	G.R.	Ft.
Net Productive Interval	145		Ft.
Estimated Porosity	8		%
All Depths Measured From	KELLY BUSHING		
Total Depth	9404		Ft.
Main Hole/Casing Size	6 1/2"		
Rat Hole/Liner Size	-		
Drill Collar Length	639'	I.D.	2.00"
Drill Pipe Length	8583'	I.D.	2.76"
Packer Depth(s)	9255 & 9259		Ft.

Sampler Pressure	1000	P.S.I.G. at Surface
Recovery: Cu. Ft. Gas	4.5	
cc. Oil	-	
cc. Water	-	
cc. Mud	175	
Tot. Liquid cc.	175	
Gravity	-	° API @ - ° F.
Gas/Oil Ratio	-	cu. ft./bbl.

CHLORIDE CONTENT

Recovery Mud	<u>.08</u>	@	<u>85</u>	°F.	
Recovery Mud Filtrate	<u>.05</u>	@	<u>70</u>	°F.	<u>200,000</u> ppm
Mud Pit Sample	<u>.1</u>	@	<u>60</u>	°F.	
Mud Pit Sample Filtrate	<u>.05</u>	@	<u>60</u>	°F.	<u>200,000</u> ppm

Mud Type SALT SATURATED Wt. 11.1
Viscosity 50 Water Loss 4.2 C.C.
Resist. of Mud .1 @ 60 °F, of Filtrate .05 @ 60 °F
Chloride Content 200,000 PPM

Remarks:

Company CORDILLERA CORPORATION Field -
Well SPILLER CANYON #1 Location SEC. 16 - T30S RANGE 25E
Test Interval 9259' TO 9404' Test # 1 Date 6-30-78

County SAN JUAN State UTAH
Technician RICHARDS (VERNAL) Test Approved By MR. JOHN REID

Field Report No. 09725 D
No. Reports Requested 15

PAGE NO. 6


FIELD REPORT NO.: 09725 D

INSTRUMENT NO.: J-303

CAPACITY: 6400#

NO. OF REPORTS: 15-

PRESSURE DATA FROM THIS CHART IS PRESENTED ON NEXT PAGE



BOTTOM HOLE PRESSURE AND TIME DATA

JOHNSTON
Schlumberger

INSTRUMENT NO.: J-303

CAPACITY(P.S.I.): 6400

DEPTH: 9264 FT.

PORT OPENING: INSIDE

BOTTOM HOLE TEMP.: 148

PAGE 1 OF 2

DESCRIPTION	LABELED POINTS	PRESSURE (P.S.I.)	GIVEN TIME	COMPUTED TIME
INITIAL HYDROSTATIC MUD	1	5386.2		
INITIAL FLOW(1)	2	909.9		
INITIAL FLOW(2)	3	946.9	28	29
INITIAL SHUT-IN	4	2795.1	35	33
FINAL FLOW(1)	5	1052.9		
FINAL FLOW(2)	7	1073.3	60	60
FINAL SHUT-IN	8	2782.4	120	121
FINAL HYDROSTATIC MUD	9	5396.5		

INCREMENTAL READINGS

LABEL POINT	DELTA TIME	PRESSURE (P.S.I.)	T + DT/DT	LOG	PW - PF (P.S.I.)	COMMENTS
1		5386.2				
2	0	909.9				HYDROSTATIC MUD
	5	898.4				INITIAL FLOW(1)
	10	894.6				
	15	901.0				
	20	913.7				
	25	926.5				
3	29	946.9				INITIAL FLOW(2)
3	0	946.9				STARTED SHUT-IN
	3	2330.5	10.667	1.028	1383.6	
	6	2682.8	5.833	0.766	1735.9	
	9	2753.0	4.222	0.626	1806.1	
	12	2772.2	3.417	0.534	1825.3	
	15	2781.1	2.933	0.467	1834.2	
	18	2784.9	2.611	0.417	1838.0	
	21	2788.8	2.381	0.377	1841.8	
	24	2790.0	2.208	0.344	1843.1	
	27	2792.6	2.074	0.317	1845.7	
	30	2793.9	1.967	0.294	1847.0	
4	33	2795.1	1.879	0.274	1848.2	INITIAL SHUT-IN
5	0	1052.9				FINAL FLOW(1)
6	3	964.8				FLOW POINT
	5	964.8				
	10	986.5				
	15	1001.8				
	20	1006.9				
	25	1005.6				
	30	1005.6				
	35	1008.2				
	40	1051.6				
	45	1068.2				
	50	1073.3				
	55	1073.3				
7	60	1073.3				FINAL FLOW(2)
7	0	1073.3				STARTED SHUT-IN

LABEL POINT	DELTA TIME	PRESSURE (P.S.I.)	T + DT/DT	LOG	PW - PF (P.S.I.)	COMMENTS
	1	1491.9	90.000	1.954	418.7	
	2	1979.5	45.500	1.658	906.2	
	3	2289.7	30.667	1.487	1216.4	
	4	2478.6	23.250	1.366	1405.3	
	5	2583.3	18.800	1.274	1510.0	
	6	2650.9	15.833	1.200	1577.6	
	7	2684.1	13.714	1.137	1610.8	
	8	2704.5	12.125	1.084	1631.2	
	9	2718.6	10.889	1.037	1645.3	
	10	2727.5	9.900	0.996	1654.2	
	12	2739.0	8.417	0.925	1665.7	
	14	2745.4	7.357	0.867	1672.1	
	16	2747.9	6.562	0.817	1674.6	
	18	2751.7	5.944	0.774	1678.5	
	20	2754.3	5.450	0.736	1681.0	
	22	2755.6	5.045	0.703	1682.3	
	24	2756.9	4.708	0.673	1683.6	
	26	2758.1	4.423	0.646	1684.8	
	28	2759.4	4.179	0.621	1686.1	
	30	2760.7	3.967	0.598	1687.4	
	35	2762.0	3.543	0.549	1688.7	
	40	2764.5	3.225	0.509	1691.2	
	45	2765.8	2.978	0.474	1692.5	
	50	2767.1	2.780	0.444	1693.8	
	55	2768.3	2.618	0.418	1695.1	
	60	2769.6	2.483	0.395	1696.3	
	65	2772.2	2.369	0.375	1698.9	
	70	2773.4	2.271	0.356	1700.2	
	75	2773.4	2.187	0.340	1700.2	
	80	2773.4	2.113	0.325	1700.2	
	85	2774.7	2.047	0.311	1701.4	
	90	2776.0	1.989	0.299	1702.7	
	95	2777.3	1.937	0.287	1704.0	
	100	2778.6	1.890	0.276	1705.3	
	105	2779.8	1.848	0.267	1706.5	
	110	2781.1	1.809	0.257	1707.8	
	115	2781.1	1.774	0.249	1707.8	
	120	2782.4	1.742	0.241	1709.1	
8	121	2782.4	1.736	0.239	1709.1	FINAL SHUT-IN
9		5396.5				HYDROSTATIC MUD

SHEPLER & THOMAS, INC.

OIL & GAS CONSULTANTS

P. O. Box 2164 Evergreen, Colorado 80439

303/674-3503

August 1, 1978

Cordillera Corporation
2334 East Third Avenue
Denver, Colorado 80206

Gentlemen:

A preliminary analysis of the drill stem test data and bottom hole pressure data available from the two wells in the Little Valley Field has been made.

The data available includes the drill stem from Cordillera's Spiller Canyon State Well No. 1, four drill stem tests from Pubco's (now Mesa) Lisbon Federal Well 2-21F, and a 72-hour build-up test in Mesa's well which was taken in January, 1978.

The extrapolation of the drill stem test build-up data shows that the original bottom hole pressure (even when corrected to the same datum) varies with the zone being tested. The pressure difference was 171 psi with the higher pressures being at the shallower depth.

Since the Mississippian formation pressure in the Little Valley Field is below the normal expected pressure gradient, the difference in original pressure in the zones tested suggests that it would be very difficult to determine if a new well had original pressure or had been affected by offset production. Based upon the drill stem data, the original reservoir pressures in the Mesa well are as follows:

<u>Zone Tested</u>	<u>Mid-point</u>	<u>Reservoir Pressure - psi</u>	<u>Pressure at Depth of 9200 feet - psi</u>
9268'-9313'	9290.5'	3155	3148
9313'-9356'	9334.5'	3041	3030
9356'-9448'	9402'	3110	3094
9446'-9518'	9482'	3000	2977

Page 2
Cordillera Corporation
August 1, 1978

An analysis of the pressure build-up test, having a radius of investigation of approximately 800 feet and taken in January, 1978, on the Mesa well, shows that the maximum average reservoir pressure at that time would not exceed 2658 psi. In fact, if a longer build-up time had been measured, I would expect an average present reservoir pressure of about 2600 psi.

The reservoir pressure of the Cordillera well is 2808 psi, which is at least 151 psi greater than the maximum expected pressure in the Mesa well.


Based upon the available drill stem test data and the pressure build-up data, I would conclude that the two wells are not connected in the zones from which the Mesa well is producing and the Cordillera well was tested.

In conclusion, I would summarize this preliminary analysis:

1. The original bottom hole pressure was not constant over the Mississippian.
2. The Mesa well and Cordillera well are not connected in the zones that have been tested in the Cordillera well to date.

Yours truly,

SHEPLER & THOMAS, INC.


James C. Shepler

CORDILLERA STATE #1
SW SW Sec. 16, T 30 S, R 25 E
Little Valley Field
San Juan County, Utah

COMPLETION REPORT

- 7/19/78 Rigged up Completion Unit. Picked up tubing. Went in hole with casing scraper. Circulated out drilling fluid. SDON.
- 7/20/78 Waiting on perforating truck. Rigged up same. SDON.
- 7/21/78 Ran Gamma Ray Correlation log and cement bond log. Top of cement at 5,806'. 100% bond from top Mississippian to top of cement. 75%-100% bonding through Mississippian. Perforated with Dresser Atlas 9048 - 52; 9068 - 71; (9085 - 90; 9090 - 98;) 9253 - 58; 9264 - 94; (9306 - 14; 9314 - 22;) 9360 - 72; 9380 - 83; 9389 - 94; 9408 - 15; and 9415 - 21, with 2/foot. Ran Model R production packer, failed to set. Came out of hole. SDON.
- 7/22/78 Ran RTTS packer, set packer at 8970'. Rigged up Halliburton, spotted 500 gals. 7 1/2% HCl with diverting agent. Broke down at 3000 lbs. treated with 2500 gals. 7 1/2% HCl and diverting agent at 3-3 1/2 BPM at 2800 lbs. Dropped 125 balls throughout treatment. Shut in 2 hours, swabbed back, starting flowing at 200 Mcfd. SDON.
- 7/23/78 T.P. 750 lbs. blew down 10 min. Fluid level at 4200 ft. Pulled two swabs. Kicked off. Steady stream about 30' of spent acid and water and gas. SDON.
- 7/24/78 T.P. 1800 lbs. opened on 11/64" choke. Flowing 530 Mcf with 1600 lbs. at 1 o'clock 14/64" flowing 2800 Mcfd with 790 lbs. 2 o'clock 11/64" 577 Mcfd with 1380 lbs. started making condensate.
- 7/25/78 Waiting on Halliburton to acidize.
- 7/26/78 Rigged up Halliburton and acidized with 25,000 gals. 15% Hcl and polymer for diverting blocks. Had pressure increases of 500 lbs and 1000 lbs from blocks. Average displacement pressure of 3000 lbs. at 7 BPM. ISIP - 300 lbs. to 0 lbs. on vacuum.
- 7/27/78 T.P. 800 lbs. blew down, pumped in 60 bbls water, pulled tubing, layed down RTTS packer and picked up Model D. Model D stopped at liner hanger. Came out of hole, went in with mill, dressed hanger. Ran and set Model D at 8970' with inhibitor on back side of tubing.
- 7/28/78 Fluid level at 2400'. Swabbed down to 4000'. Well started flowing. Flowed water and spent acid until dark. SDON.

CORDILLERA STATE #1 - LITTLE VALLEY

COMPLETION REPORT (Cont')

7/29/78 SITP 1160 lbs. Blew down. Made two swab runs. Well flowing distillate, water and spent acid.

11:00 a.m.	18/64	210 lbs.	1" water
12:00 a.m.	"	250 lbs.	"
1:00 p.m.	"	400 lbs.	water decreasing
2:00 p.m.	"	500 lbs.	spray H ₂ O
Making 2 MMcfd			
3:00 p.m.	18/64	550 lbs.	spray - 2.046 MMcf
4:00 p.m.	19/64	600 lbs.	" 2.341 "
5:00 p.m.	"	690 lbs.	" 2.864 "
6:30 p.m.		770 lbs.	
7:30 p.m.		790 lbs.	
8:30		800 lbs.	

Released rig. SDON.

7/30/78 SITP 1890 lbs.

10:00 a.m. 1200 lbs. 3 MMcfd
Flowing to clean up. Flare will not keep burning due to water.
Shut in, waiting on separator.

8/12/78 Hooked up separator.

8/13/78- Flowed and flared off and on while cleaning up well -- approximately
8/17/78 4000 Mcf total. Shut well in for pressure buildup.

8/31/78 Tefteller, Inc., ran pressure bomb prior to four-point test.
Shut-in pressure @ 8850' = 2749 psia

<u>Choke</u>	<u>Vol. in Mcf</u>	<u>Flowing BHP psia</u>
24/64	3615	1892
19/64	2938	1980
16/64	2180	2116
12/64	1382	2259

Shut in for 72-hr. buildup.

9/5/78 Pulled bomb. Shut well in. Waiting for pipeline connection.

CORDILLERA CORPORATION

2334 EAST THIRD AVENUE • DENVER, COLORADO 80206 • (303) 355-3535

F.H.
4 August 1978

DIVISION OF OIL, GAS AND MINING
STATE OF UTAH
1588 West North Temple
Salt Lake City, Utah 84116

ATTENTION: MR. P. L. DRISCOLL

RE WELL STATUS REPORT
State #1, Cordillera
Sec. 16, T 30 S, R 25 E
San Juan County, Utah


Gentlemen:

We are still in the process of completing subject well, but will update you prior to filing our completion report.

We ran a cement bond log (copy enclosed) and perforated 104' of porosity in intervals from 9048' to 9421', with 2 shots per foot. Ran a small cleanup acid job of 3000 gallons 7½% HCl and 125 ball sealers. Flowed back water and spent acid. Final rate of 2800 Mcfd on 14/64 choke and 790 lbs. on tubing. Acidized with 25,000 gallons 15% HCl and two polymer diverting plugs. First plug caused a 500-lb. increase, and the second, a 1000-lb. increase. Displaced at 3000 lbs. and 7 BPM. Flowed back spent acid and water, with a final rate of 3000 Mcfd on 6/64 choke and 1200 lbs on tubing. Shut in, waiting on equipment to run multi-point test.

We had Jim Shepler do a preliminary analysis on the tests available. Enclosed is a copy of his letter for your information.

Very truly yours,


JACK M. LUCEY

JML/nll

CORE LABORATORIES, INC.

Petroleum Reservoir Engineering

DALLAS, TEXAS

September 1, 1978

Page 1 of 1File RFL 78577

Company Cordillera Corporation Formation
Well Spiller Canyon State No. 1 County San Juan
Field Wildcat State Utah

HYDROCARBON ANALYSIS OF GAS SAMPLE


COMPONENT	MOL PER CENT	GPM
Hydrogen Sulfide	0.84	
Carbon Dioxide	13.97	
Nitrogen	10.37	
Methane	66.33	
Ethane	5.47	1.455
Propane	1.76	0.482
iso-Butane	0.39	0.127
n-Butane	0.50	0.157
iso-Pentane	0.17	0.062
n-Pentane	0.11	0.040
Hexanes	0.06	0.024
Heptanes plus	0.03	0.014
	100.00	2.361

Calculated gas gravity (air = 1.000) = 0.801

Calculated gross heating value = 858 BTU per
cubic foot of dry gas at 14.65 psia at 60°F.

Collected at 300 psig and 32 °F.

Core Laboratories, Inc.

P. L. Moses, Manager
Reservoir Fluid Analysis

PLM:RB:lf

7 cc: Mr. Jack Lucy
Cordillera Corporation
2334 E. 3rd Avenue
Denver, Colorado 80206


CORDILLERA CORPORATION

2334 EAST THIRD AVENUE

DENVER, COLORADO 80206

(303) 355-3535

12 September 1978



DIVISION OF OIL, GAS & MINING
Department of Natural Resources
State of Utah
1588 West North Temple
Salt Lake City, Utah 84116

RE CORDILLERA STATE #1
Little Valley Field
San Juan County, Utah

ATTENTION: MR. PATRICK L. DRISCOLL
Chief Petroleum Engineer

Gentlemen:

Please find enclosed the completion report on the subject well. Attached to the report is a copy of the gas analysis, along with our daily completion report, which covers the completion in somewhat more detail.

We are also enclosing a copy of the latest gas analysis of Mesa's 2-21F well for your information.

Very truly yours,

JACK M. LUCEY
Engineer

JML/n11

Enclosures

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 42-R355.5.

13

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	Other _____		
b. TYPE OF COMPLETION:							
NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____							
2. NAME OF OPERATOR Cordillera Corporation							
3. ADDRESS OF OPERATOR 2334 East Third Avenue, Denver, Colorado 80206							
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*							
At surface 500' FSL, 500' FWL, Sec. 16							
At top prod. interval reported below 496' FSL, 515' FWL, Sec. 16							
At total depth 460' FSL, 509' FWL, Sec. 16							
14. PERMIT NO.		DATE ISSUED					
43-037-11356		2/17/78					
15. DATE SPUDDED		16. DATE T.D. REACHED		17. DATE COMPL. (Ready to prod.)			
5/22/78		7/3/78		9/5/78			
18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*		19. ELEV. CASINGHEAD					
6861' RKB		6847'					
20. TOTAL DEPTH, MD & TVD		21. PLUG, BACK T.D., MD & TVD		22. IF MULTIPLE COMPL., HOW MANY*			
9517' - 9468' <i>dd 9468'</i>		--		--			
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*					25. WAS DIRECTIONAL SURVEY MADE		
9048' - 9004' Mississippian - Leadville					yes		
9421' - 9373' Mississippian - Leadville							
26. TYPE ELECTRIC AND OTHER LOGS RUN					27. WAS WELL CORED		
Dual Laterolog, Compensated Neutron-Formation Density, Borehole Compensated Sonic - GR - Caliper, Cement Bong Log					no		
28. CASING RECORD (Report all strings set in well)							
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED		
10 3/4"	32.75	1000' KB	13 3/4	475 Sx	none		
7 5/8"	29.70	5155' KB	9 7/8	900 Sx	none		
4 1/2"	11.60	9507' KB	6 3/4 - 6 1/2	550 Sx	none		
29. LINER RECORD			30. TUBING RECORD				
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
4 1/2"	4526' KB	9507' KB	550 Sx		2 3/8	8970+'	8970'
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
2 shots/ft. of .39" in the following:				DEPTH INTERVAL (MD)			AMOUNT AND KIND OF MATERIAL USED
9048-52; 9068-71; 9085-98; 9253-58; 9264-94;				8970 - 9507			2500 gals. 7 1/2% HCl w/125 ball sealers
9306-22; 9360-72; 9380-83; 9389-94 & 9408-21				8970 - 9507			25,000 gals. 15% HCl & 2 polymer diverting blocks
33.* PRODUCTION							
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)			WELL STATUS (Producing or shut-in)		
7/28/78		flowing			shut-in		
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
8/31/78*	16	various	→	33	1686	15	50:1
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
various	packer	→	72	3615	nil	--	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)					TEST WITNESSED BY		
Flared					John Reid		
35. LIST OF ATTACHMENTS							
Gas analysis. *Completion Report.							
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records							
SIGNED <i>John M. Lacey</i>		TITLE <i>Engineer</i>		DATE <i>9/12/78</i>			

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.


Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES			38. GEOLOGIC MARKERS			
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TRUE VERT. DEPTH
Mississippian Leadville	9259	9404	DST: Bomb @ 9264 - 2000' water cushion. Open 30", Shut-in 30" Open 60", Shut-in 120" IH 5398; FH 5398; IO 869-933; ISI 2782; FO 971-1060; FSI 2782. Gas to surface 47 mins., 1 1/2" blow in 5 gal. bucket increase to bottom in 5 mins. Increased to 28 lbs in 10 mins. 2nd flow reopened @ 28 lb., decreased to 8 lb., pro- duced water cushion and then increased to 60 lbs. - 450 Mcfd - steady.	Lower Hermosa Molas Mississippian Dolomite	8833 8956 8993 9243	8788 8913 8950 9196



November 10, 1978



State of Utah
Division of Oil, Gas, and Mining
1588 West North Temple
Salt Lake City, Utah 84116

Attention: Mr. Cleon B. Feight
Mr. Pat Driscoll

Re: Spiller Canyon State #1
Sec. 16, T. 30 S., R. 25 E.,
San Juan County, Utah
Cordillera Corporation

Gentlemen:

In response to your October 31, 1978 letter relating to the above, a meeting was held yesterday in Mesa's Amarillo office between Mesa and Cordillera. An agreement was reached as to the required testing procedure under Order in Cause No. 70-2. The procedure will involve approximately one week's time with pressure bomb bottom hole measurements on each end and dead weight testing in between, along with surface pressure measurements.

The physical testing procedure should take about two weeks and an additional two weeks or so will be required for analysis. Mesa and Cordillera shall contact the Board upon completion of the analysis.

Very truly yours,

MESA PETROLEUM CO.

A handwritten signature in cursive script, appearing to read 'Jed W. Lemmons'.

Jed W. Lemmons
Division Land Manager

JWL:dj
cc: Mr. James N. Blue
Mr. Les Carnes

CORDILLERA CORPORATION
2334 EAST THIRD AVENUE
DENVER CO 80206
ATTN: LETTIE FLOWER

PHONE: 303-355-3535

YOUR UTAH ACCOUNT NUMBER: N0270
PRODUCING ENTITY NUMBER: 02555
PRODUCING ENTITY NAME : LITTL VALLY STATE #1

API	ZONE	WELL NAME	SECTION	TOWNSHIP	RANGE	QTR-QTR
✓ 43-037-11356	LDLL	SPIRER-CYN ST #1 <u>Cordillera</u>	16	30.0-S	25.0-E	SWSW

Sundry

name
change

Wmell



DOGMA 56-64-2
an equal opportunity employee

Page 2 of 2

Operator name and address:

•CORDILLERA CORPORATION
5031 S ULSTER PKY #410
DENVER CO 80237
ATTN: LETTIE FLOWER

AUG 3 1 1987

Utah Account No. N0270

Report Period (Month/Year) 7 / 87

Amended Report ☐

Well Name	Producing	Days	Production Volume		
API Number Entity Location	Zone	Oper	Oil (BBL)	Gas (MSCF)	Water (BBL)
H.E. WALTON A-3 4301516023 02550 14S 07E 30.	FRSD	-			
P.T. WALTON 1-X 4301516024 02550 14S 07E 19	FRSD	-			
CORDILLERA ST #1 4303711356 02555 30S 25E 16	LDLL	-	***		
FEDERAL T-20 4303730464 02560 30S 25E 20	LDLL	-	***		
TOTAL					

Comments (attach separate sheet if necessary)

~~D~~ ***Effective July 1, 1987, the new Operator for Cordillera ST #1 and Federal 1-20
is GASCO, Inc., PO Box 15277, Lakewood, CO 80215 N0535

I have reviewed this report and certify the information to be accurate and complete. Date August 27, 1987

Authorized signature _____

Ruth Sullivan, Controller

Telephone (303) 779-8811

PLEASE COMPLETE FORMS IN BLACK INK

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT TRIPPLICATE
(Other instructions on
reverse side)

PGW

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML 26505 PEN #02555	
2. NAME OF OPERATOR GSC Operating Co.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME 092902	
3. ADDRESS OF OPERATOR P.O. Box 15277 Lakewood, CO 80215		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 500' FSL & 500' FWL Sec 16-T30S-R25E SLP		8. FARM OR LEASE NAME State	
14. PERMIT NO. 43-037-11356		9. WELL NO. #1 Cordillera	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 6847'		10. FIELD AND POOL, OR WILDCAT Little Valley	
		11. SEC., T., R., M., OR BLK. AND SUBST OR AREA Sec. 16-T30S-R25E	
		12. COUNTY OR PARISH San Juan	
		13. STATE Utah	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	FULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	

(Other) Change of Operator

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Change Operator from Cordillera Corporation to GSC Operating Co. effective 7-1-87.

RECEIVED
SEP 29 1987
DIVISION OF OIL
GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED Yeg Beckman TITLE Production Tech. DATE 9-23-87

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

WELL NO. State Spiller #1 San Juan Co. Utah
(re-entry of Pure Oil Co. well of same name)

10³/₄" @ 999'

← liner hanger @ 4520'

7⁵/₈" @ 5155'

— 5750' Tp. Cmt

— 6300' wth. level static

2³/₈"

← 7200' Tp of fish

9-1-78 CAOF (4 pt) 13.13 MMCFPD

Mississippian Leadville

DST 9259-9404 30-30-60-120

GTS 47min 480 MCFPD steady

>2000 ppm H₂S

IFP 869-923

ISIP 2782#

FFP 971-1060

FSIP 2782#


Model "D" pKr set @ 8970' on 7-27-78 (inhibited fluid on backside)

9048-52	9306-14	IP Mississippian Leadville w/2 spf 7-21-78
9068-71	9314-22	Acidized w/3000 gal 7 ¹ / ₂ % HCl 7-22-78
9085-90	9360-72	Flowed on 1 ¹ / ₄ " CK 790# FTP 2800 MCFPD
9090-98	9380-83	Acidized w/25,000 gal 15% HCl w/polymer diverter
9253-58	9389-94	
9264-94	9408-15	
	9415-21	


4¹/₂" 11.6# N-80 osg set on 7-5-78 w/450 sx lite + 100 sx reg.
9507'

Updated thru 5-28-87

JAA



Source: Four Corners Geologic Society (1978).



STRUCTURE MAP
LITTLE VALLEY FIELD
San Juan County, Utah
Datum: Top of Leadville
C. I. 250 Feet

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
DRILLING AND WELL PLUGGING INSPECTION FORM

COMPANY: West Hazmat COMPANY MAN: Kent Stringham
WELL NAME: Cordillera State #1 API #: 43-037-11356
QTR/QTR: SW/SW SECTION: 16 TWP: 30S RANGE: 25E
CONTRACTOR: B+B Well Ser PUSHER/DRLR: _____
INSPECTOR: Glenn DATE: 3/24/92 OPERATIONS: P4H
SPUD DATE: _____ TOTAL DEPTH: _____

DRILLING AND COMPLETIONS

____ APD ____ WELL SIGN ____ BOPE ____ RESERVE PIT
____ FLARE PIT ____ BURN PIT ____ H2S ____ BLOOIE LINE
____ SANITATION ____ HOUSEKEEPING ____ VENTED/FLARED

PLUGGING AND ABANDONMENT

PRODUCING FM(S): _____

PLUGS:	TYPE/SIZE	INTERVAL
	<u>4 1/2 CIBP</u>	<u>16400' + -</u>
	<u>30SKs CMT-silica CLG</u>	<u>16400' - 16022'</u>
	<u>70SKs</u>	<u>4727' - 4326'</u>
	<u>210SKs</u>	<u>2700' - 1800'</u>
	<u>25SKs</u>	<u>1050' - 950'</u>
PERFORATIONS:	<u>50SKs</u>	<u>215' - 0'</u>

CASING SIZE: _____ PULLED: YES / NO CUT AT: _____

PLUGS TESTED: _____ HOW: _____ WOC: _____

MARKER: _____ SURFACE: _____ PLATE: _____

RECLAMATION:

CONTOURED: _____ RIPPED: _____ REHAB'D: _____

LEGEND: (Y)-YES (P)-PROBLEM (U)-UNKNOWN (BLANK)-NOT APPLICABLE

REMARKS: Dug out cellar to cmt. 10 3/4 but 10 3/4 had been cut off
& cmt to surface. cut 7 5/8' + w/11 welded plate on below
Plw line

DATE 12/06/91

PRODUCTION INQUIRY SCREEN

MENU: OPTION 00

TWNSHP RANGE SC SPOT MD. API ZONE STATUS
30.0 S 25.0 E 16 SWSW S 43-037-11356 LDLL PGW

OPERATOR: N0535 : GASCO, INC. (DBA GSC OPER)

WELL NAME: CORDILLERA ST #1

ENTITY: 2555 : CORDILLERA ST #1

ACCT	ENTY	DAYS	OIL PROD	GAS PROD	WATER	PROD	PERIOD
CUM THRU 12/31/90			1254.00	2229551.00		0.00	
N0535	2555	27	0.00	872.00		0.00	91-01
N0535	2555	28	0.00	751.00		0.00	91-02
N0535	2555	0	0.00	0.00		0.00	91-03
N0535	2555	26	0.00	1094.00		0.00	91-04
N0535	2555	29	0.00	1088.00		0.00	91-05
N0535	2555	30	0.00	1007.00		0.00	91-06
N0535	2555	31	0.00	953.00		0.00	91-07
N0535	2555	1	0.00	26.00		0.00	91-08
N0535	2555	0	0.00	0.00		0.00	91-09
N0535	2555	0	0.00	0.00		0.00	91-10
YTD			0	5,791		0	

OPTION: 13 PERIOD(YMM): 9100 API: 4303711356 ZONE: LDLL ENTITY: 11078

DATE 12/06/91

PRODUCTION INQUIRY SCREEN

MENU: OPTION 00

TWNSHP RANGE SC SPOT MD. API ZONE STATUS
30.0 S 25.0 E 16 SWSW S 43-037-11356 LDLL PGW

OPERATOR: N0535 : GASCO, INC. (DBA GSC OPER)

WELL NAME: CORDILLERA ST #1

ENTITY: 2555 : CORDILLERA ST #1

ACCT	ENTY	DAYS	OIL PROD	GAS PROD	WATER PROD	PERIOD
CUM THRU 12/31/90			1254.00	2229551.00	0.00	
N0535	2555	31	0.00	888.00	0.00	90-01
N0535	2555	26	0.00	693.00	0.00	90-02
N0535	2555	30	0.00	1132.00	0.00	90-03
N0535	2555	29	0.00	1092.00	0.00	90-04
N0535	2555	31	0.00	1282.00	0.00	90-05
N0535	2555	23	0.00	1013.00	0.00	90-06
N0535	2555	31	0.00	1019.00	0.00	90-07
N0535	2555	31	0.00	944.00	0.00	90-08
N0535	2555	26	0.00	887.00	0.00	90-09
N0535	2555	31	0.00	936.00	0.00	90-10
N0535	2555	30	0.00	834.00	0.00	90-11
N0535	2555	28	0.00	819.00	0.00	90-12
YTD			0	11,539	0	

OPTION: 13 PERIOD(YMM): 9000 API: 4303711356 ZONE: LDLL ENTITY: 11078

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR Gasco, Inc. (dba GSC Operating)		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR P.O. Box 281304, Lakewood, Colorado 80228		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 500' FSL, 500' FWL		8. FARM OR LEASE NAME State
14. API NUMBER 43-037-11356		9. WELL NO. #1 Cordillera
15. ELEVATIONS (Show whether DF, NT, OR, etc.) GL 6847'		10. FIELD AND POOL, OR WILDCAT Little Valley
		11. SEC., T., R., M., OR PLK. AND SURVEY OR AREA Sec. 16, T30S, R25E S.L.B.M.
		12. COUNTY OR PARISH San Juan
		13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	<input type="checkbox"/>	WATER SHUT-OFF	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	FRACTURE TREATMENT	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	SHOOTING OR ACIDIZING	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	(Other) Well Status	<input type="checkbox"/>
(Other)	<input type="checkbox"/>	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	
FULL OR ALTER CASING	<input type="checkbox"/>	REPAIRING WELL	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	ALTERING CASING	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	ABANDONMENT*	<input type="checkbox"/>
CHANGE PLANS	<input type="checkbox"/>		

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) *

Shut in well on August 2, 1991. It is requested that temporarily abandoned status be given on this well for a twelve month period, until a more favorable gas market exists.

18. I hereby certify that the foregoing is true and correct

SIGNED Dana K. Smith TITLE Engineering Technician DATE 12/11/91

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

Form OGC-1b

SUBMIT IN TRIPLICATE*
(Other instructions on
reverse side)STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR WEST HAZMAT OIL FIELD SERVICES, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 201 N. VERNAL AVE. #1, VERNAL, UTAH 84078		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 500' FSL & 500 FWL SW $\frac{1}{4}$, SW $\frac{1}{4}$		8. FARM OR LEASE NAME STATE
14. PERMIT NO. 43-037-11356		9. WELL NO. SPILLER # 1
15. ELEVATIONS (Show whether OF, RT, OR, etc.) 6861' RKB		10. FIELD AND POOL, OR WILDCAT LITTLE VALLEY
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SEC. 16, T.30S., R.25E
		12. COUNTY OR PARISH SAN JUAN
		13. STATE UTAH

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF	<input type="checkbox"/>	FULL OR ALTER CASING	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	MULTIPLE COMPLETE	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	ABANDON*	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	CHANGE PLANS	<input type="checkbox"/>
(Other)			

SUBSEQUENT REPORT OF:

WATER SHUT-OFF	<input type="checkbox"/>	REPAIRING WELL	<input type="checkbox"/>
FRACTURE TREATMENT	<input type="checkbox"/>	ALTERING CASING	<input type="checkbox"/>
SHOOTING OR ACIDIZING	<input type="checkbox"/>	ABANDONMENT*	<input type="checkbox"/>
(Other) TEST			

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

OPERATOR WISHES TO REPORT THAT A CASING INTEGRITY TEST WILL BE CONDUCTED ON THE SUBJECT WELL. IN ADDITION THE OPERATOR PROPOSES TO CONDUCT A STEP RATE INJECTION TEST. DATA FROM THE CASING AND STEP RATE TEST WILL BE USED TO EVALUATE THE POSSIBLE CONVERSION OF THE WELL TO A SALT WATER INJECTION WELL.

*APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 1-22-92

BY: [Signature]

RECEIVED

JAN 09 1992

* Operator will keep the Division appraised of all testing activity to allow witnessing and consultation. Following a reasonable test period and application for injection, the well will be discussed with Division staff.

DIVISION OF
OIL, GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED William A. Ryan / Agent

TITLE Operations Manager
Rock Mt. Consulting

DATE 12/8/91

(This space for Federal or State office use)

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

DOCM Form 5
May 5, 1987STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR GASCO, INC. (dba GSC Oper)		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR P.O. Box 281304, Lakewood, Colorado 80228		7. UNIT ACCESSION NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 500' FSL & 500' FWL		8. FARM OR LEASE NAME State
10. API NUMBER 43-037-11356		9. WELL NO. 1
11. ELEVATIONS (Show whether OF, RT, GA, etc.) 6861' RKB		10. FIELD AND POOL, OR WILDCAT Little Valley
12. COUNTY OR PARISH San Juan		11. SEC., T., R., M., OR ALK. AND SURVEY OR AREA 16-T30S-R25E, S1BM
13. STATE UT		

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

☐

FULL OR ALTER CASING

☐

FRACTURE TREAT

☐

MULTIPLE COMPLETE

☐

SHOOT OR ACIDIZE

☐

ABANDON*

☐

REPAIR WELL

☐

CHANGE PLANS

☐

(Other)

☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

☐

REPAIRING WELL

☐

FRACTURE TREATMENT

☐

ALTERING CASING

☐

SHOOTING OR ACIDIZING

☐

ABANDONMENT*

☐

(Other)

☐

Change of Operator

☒

(Note: Report results of multiple completion or Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Notice is hereby given that effective January 6, 1992 the Above
mentioned well is operated by:

West Hazmat Oil Field Services, Inc.
201 N. Vernal Ave. #1
Vernal, Utah 84078

RECEIVED

JAN 09 1992

DIVISION OF
OIL, GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE

Engineer Technician

DATE

January 6, 1992

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS (Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)		3. LEASE DESIGNATION AND SERIAL NO. ML 26505
1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR West Hazmat Oil Field Services, Inc.		7. UNIT AGREEMENT NAME
3. ADDRESS OF OPERATOR 201 N. Vernal Ave. #1, Vernal, Utah 84078		8. FARM OR LEASE NAME State
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 500' FSL & 500' FWL		9. WELL NO. 1
14. API NUMBER 43-037-11356		10. FIELD AND POOL, OR WILDCAT Little Valley
15. ELEVATIONS (Show whether DP, RT, OR, etc.) 6861' RKB		11. SEC., T., R., M., OR ALK. AND SURVEY OR AREA 16-T30S-R25E, SLBM
		12. COUNTY OR PARISH 13. STATE San Juan Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	FULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) Change of Operator <input checked="" type="checkbox"/>	
(Other) <input type="checkbox"/>		(Note: Report results of multiple completion or Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Notice is hereby given that Effective January 6, 1992, West Hazmat Oil Field Services, Inc. is the operator of the State #1 Well.

RECEIVED

JAN 09 1992

DIVISION OF
OIL, GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Vice President DATE 1-7-92

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY: _____

Form OGC-1b

SUB IN TRIPLICATE*
(Carry instructions on
reverse side)STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML 26505	
2. NAME OF OPERATOR WEST HAZMAT OIL FIELD SERVICES, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 201 N. VERNAL AVE. #1, VERNAL, UTAH 84078		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 500' FSL & 500 FWL SW $\frac{1}{4}$, SW $\frac{1}{4}$		8. FARM OR LEASE NAME STATE	
14. PERMIT NO. 43-037-11356		9. WELL NO. SPILLER # 1	
15. ELEVATIONS (Show whether OF, ST, OR, etc.) 6861' RKB		10. FIELD AND POOL, OR WILDCAT LITTLE VALLEY	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SEC. 16, T.30S., R.25E	
		12. COUNTY OR PARISH SAN JUAN	13. STATE UTAH

18. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	<input type="checkbox"/>

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) TEST <input type="checkbox"/>	<input type="checkbox"/>

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

OPERATOR WISHES TO REPORT THAT A CASING INTEGRITY TEST WILL BE CONDUCTED ON THE SUBJECT WELL. IN ADDITION THE OPERATOR PROPOSES TO CONDUCT A STEP RATE INJECTION TEST. DATA FROM THE CASING AND STEP RATE TEST WILL BE USED TO EVALUATE THE POSSIBLE CONVERSION OF THE WELL TO A SALT WATER INJECTION WELL.

RECEIVED

JAN 09 1992

DIVISION OF
OIL, GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED William A. Ryan / AgentTITLE Operations ManagerRocky Mt. ConsultingDATE 12/8/91

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____

WEST HAZMAT

Oil Field Services, Inc.

January 7, 1992

Mr. Ed Bonner
Utah division of State Land and Forestry
355 West North Temple
3 Triad Center
Salt Lake City, Utah 84180

RE: Change of operator/well bond
Spiller Canyon State #1
550' fsl 500' fwl Sec.16, Twp.30S., Rge.35E.
San Juan County, Utah


API#4303711356, Lease # 26505

Dear Mr. Bonner:

West Hazmat Oil Field Services has taken over operation of the above captioned well from Gasco. Attached is a Certificate of Deposit in the amount of \$20,000 in lieu of a well bond. It is our intention to let the existing lease expire and apply for a special use permit to convert the well into a commercial class II injection well. We plan to test the well within the week and apply for a special use permit once we have acquired our test data.

Mr. Bill Ryan of Rocky Mountain Consulting has been retained by West Hazmat Oil Field Services to test and re-complete the well. If you have any technical questions please feel free to contact Bill at 801-789-0968 or myself at 801-789-9584.

Sincerely,



Steve Rooney
Vice President

RECEIVED

JAN 09 1992

DIVISION OF
OIL, GAS & MINING

c.c. Bill Ryan



First Interstate Bank First Interstate Bank
of Utah, N.A.

TIME DEPOSIT RECEIPT AND AGREEMENT
NON-TRANSFERABLE & NON-NEGOTIABLE

178365

Office **VERNAL**

Date **010692**

Amount **20,000.00**

Name(s) and Address **UTAH DIVISION OF STATE
LAND AND FORESTRY AND
WEST HAZMAT OIL FIELD SER.
7670 S. VAUGHN SUITE 200**

ENGLEWOOD,, CO

80112

Home Phone # **801-789-9584**

Work Phone # **801-789-9584**

("Registered Owner(s)") has (have) deposited the sum of *****Twenty Thousand, and 00/100*****

payable to the Registered Owner(s) upon request **1** YR after the date hereof (date of "maturity"), with
interest at the rate of **3.630** percent per annum from the date hereof to maturity.

THIS TIME DEPOSIT MATURES ON DATE OF MATURITY AND SHALL BE DEEMED RENEWED, AND MATURITY EXTENDED, FOR SUCCESSIVE LIFE
PERIODS AT THE EFFECTIVE RATE OF INTEREST ON MATURITY DATE, UNLESS TIME DEPOSIT IS WITHDRAWN.

Tax Identification Number of Registered Owner: **841082252** **Y**

Authorized
Signature

Karen Olsen

52010915

Type **42** Customer # **0006130**

New or
Existing # **N**

Interest
Frequency **QUARTERLY**

Int. Pay
Option **DDA**

Acct # to Credit
Checking:

Maturity Date

Savings:

IRA INFORMATION

Tax Year

Birth Date

Type of Funds

SEE REVERSE SIDE FOR IMPORTANT DISCLOSURE, WITHDRAWAL, AND AUTOMATIC RENEWAL TERMS. EARLY WITHDRAWAL SUBJECT TO SUBSTANTIAL PENALTY.
I agree to all terms as stated on this receipt and certify, under penalty of perjury, that the Tax I.D. number above is correct and that I am not subject to backup withholding.

CUSTOMER COPY

TD-127U (4-91) C

[Signature]

Customer's Signature

RECEIVED

JAN 09 1992

**DIVISION OF
OIL, GAS & MINING**

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:	
1-UCR	7-MCR
2-DTS	275
3-VLC	✓
4-RJF	✓
5-RWM	✓
6-ADA	✓

Attach all documentation received by the division regarding this change.
Initial each listed item when completed. Write N/A if item is not applicable.

☒ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☐ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 1-6-92)

(new operator)	<u>WEST HAZMAT OIL FIELD</u>	FROM (former operator)	<u>GASCO, INC. (DBA GSC OPER.)</u>
(address)	<u>SERVICES, INC.</u>	(address)	<u>P. O. BOX 281304</u>
	<u>201 N. VERNAL, AVE #1</u>		<u>LAKEWOOD, CO 80228-9304</u>
	<u>VERNAL, UT 84078</u>		
	<u>phone (801) 789-9584</u>		<u>phone (303) 980-9340</u>
	<u>account no. N 9190</u>		<u>account no. N0535</u>
	<u>STEVE ROONEY, VP</u>		

Well(s) (attach additional page if needed):

Name: <u>CORDILLERA ST #1/LDLL</u>	API: <u>43-037-11356</u>	Entity: <u>2555</u>	Sec <u>16</u> Twp <u>30S</u> Rng <u>25E</u>	Lease Type: <u>ML-26505</u>
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____ Twp _____ Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). (Rec'd 1-9-92)
2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form). (Rec'd 1-9-92)
3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) ____ If yes, show company file number: #131140.
4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (1-14-92)
6. Cardex file has been updated for each well listed above. (1-14-92)
7. Well file labels have been updated for each well listed above. (1-14-92)
8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (1-14-92)
9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

Y REVIEW

(Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).

State Lands and the Tax Commission have been notified through normal procedures of entity changes.

VERIFICATION (Fee wells only)

(Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.

A copy of this form has been placed in the new and former operators' bond files.

The former operator has requested a release of liability from their bond (yes/no) ____.
Today's date _____ 19____. If yes, division response was made by letter dated _____ 19____.

E INTEREST OWNER NOTIFICATION RESPONSIBILITY

(Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated _____ 19____, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.

Copies of documents have been sent to State Lands for changes involving State leases.

NG

All attachments to this form have been microfilmed. Date: January 23 1992.

Copies of all attachments to this form have been filed in each well file.

The original of this form and the original attachments have been filed in the Operator Change file.

TS

Speed Letter®

To Ed Bonner

From Don Staley

State Lands

Oil, Gas and Mining

Subject Operator Change

— No. 9 & 10 FOLD

MESSAGE

Date 1-16 19 92

Ed,

For your information, attached are copies of documents regarding an operator change on a state lease(s). These companies have complied with our requirements. Our records have been updated. Bonding should be reviewed by State Lands ASAP.

Former Operator: CASCO INC. (dba CSC Oper)

New Operator: WEST HAZMAT OIL FIELD SERVICES INC.

Well: Cordillera State 1 API: 43-037-11356 Entity: 02555 S-T-R: 16-305-256

— No. 9 FOLD

— No. 10 FOLD

CC: Operator File

Signed

Don Staley

REPLY

Date _____ 19 ____

— No. 9 & 10 FOLD

Signed

PA'd 6-5-63
w/ 10' cont plug
in top of 7 7/8 casing
Installed D.H.M.

conductor
- 20' set @ 15'

10 7/8" @ 1000' Cont to Surface

10.7 ppm mud
80 vis

cont plug { 5000'
5300'

cont
plug

7 7/8 @ 5155'
cont plug across bit of casing

cont
plug

9025

9275

11.1 vis

cont plug

9425


9475

50' plug

9661' MD TD

Survey Directional survey dated
Jan 7, 1965 MD 9450' TVD 94412.20
503.77 N } from surface loc.
492.71 E

42-381 50 SHEETS 5 SQUARE
42-382 100 SHEETS 5 SQUARE
42-389 200 SHEETS 5 SQUARE
MADE IN U.S.A.



CEMENTING SERVICE REPORT

DS-496 PRINTED IN U.S.A.

DOWELL SCHLUMBERGER INCORPORATED

TREATMENT NUMBER

S-06-3950

DATE

2-13-92

AGE

DS

DISTRICT

FARMINGTON

WELL NAME AND NO.

State #1

LOCATION (LEGAL)

Sec 16 30S 25E.

FIELD-POOL

FORMATION

RIG NAME:

S + S

COUNTY/PARISH

SAN JUAN

STATE

UTAH

API. NO.

NAME

WEST HAZMAT

AND

7670 So Bond Court #200

ADDRESS

ENGLEWOOD, COLO

ZIP CODE 80112

SPECIAL INSTRUCTIONS

WELL DATA:

BOTTOM

TOP

BIT SIZE

CSG/Liner Size

TOTAL DEPTH

WEIGHT

☐ ROT ☐ CABLE

FOOTAGE

MUD TYPE

GRADE

☐ BHST☐ BHCT

THREAD

MUD DENSITY

LESS FOOTAGE

SHOE JOINT(S)

TOTAL

MUD VISC.

Disp. Capacity

NOTE: Include Footage From Ground Level To Head In Disp. Capacity

Float
DEPTH
TYPE
DEPTHStage Tool
DEPTH
TYPE
DEPTH

Head & Plugs

☐ TBG☐ D.P.

SQUEEZE JOB

☐ Double

SIZE

☐ Single☐ WEIGHT

TOOL

TYPE

DEPTH

☒ Swage☐ GRADE

TAIL PIPE: SIZE

DEPTH

☐ Knockoff☐ THREAD

TUBING VOLUME

Bbls

TOP ☐ R ☐ W☐ NEW ☐ USED

CASING VOL. BELOW TOOL

Bbls

BOT ☐ R ☐ W

DEPTH

TOTAL

Bbls

IS CASING/TUBING SECURED?

☐ YES ☐ NO

LIFT PRESSURE

PSI

CASING WEIGHT ÷ SURFACE AREA
(3.14 x R²)

PRESSURE LIMIT

2000 TBG

PSI

BUMP PLUG TO

PSI

ROTATE

RPM

RECIPROCATATE

FT

No. of Centralizers

ARRIVE ON LOCATION

TIME: 1230

DATE: 2-13

LEFT LOCATION

TIME:

DATE:

TIME

PRESSURE

VOLUME

PUMPED BBL

JOB SCHEDULED FOR

TIME: Noon

DATE: 2-13

SERVICE LOG DATA

0001 to 2400

TBG

OR D.P.

CASING

INCREMENT

CUM

INJECT

RATE

FLUID

TYPE

FLUID

DENSITY

1230

1413

1415

1425

1428

1445

1448

1456

1515

1517

1532

1534

1544

1553

1556

1602

1612

20

220

460

800

610

720

740

910

2000

1710

460

1560

780

380

1380

21

21

26 1/2

41

45

627

85

11.4

31.3

10.9

0

0

0

1 1/4

4

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

2

2

2

3

2 1/4

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

1.2

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

H2O

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

8.3

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

15.8

CEMENTING SERVICE REPORT SUPPLEMENT LOG

DS-496-1 PRINTED IN U.S.A.

WEST HAZMAT

DATE

2-13-92

CUSTOMER WELL NAME AND NUMBER

State #1

LOCATION (LEGAL)

Sec 16 30S 25E

DS LOCATION

Farmington

TREATMENT NUMBER

15-06-2950

PAGE

2

OF 2

PAGES

TIME 0001 to 2400	PRESSURE		VOLUME PUMPED BBL		INJECT RATE	FLUID TYPE	FLUID DENSITY	SERVICE LOG DETAIL
	TBG OR D.P.	CASING	INCREMENT	CUM				
1625		500			1 1/2	H2O	8.3	Rtg pull 5 stds TBG (Dry)
1626		1100			3	"	"	Try to Reverse Circ
1628		1360	8.8		3	"	"	Return slowing way down
1629		1360	10.8		3			Inc RATE.
1630	690					H2O	8.3	Shut down - NO RETURNS
1631	2000							Try Circulating
1633								Shut down PSI
1633	3500		1/2			H2O	8.3	Bleed off PSI fast.
1636	3500							Try Circ down TBG AGAIN
								Inc MAX PSI -
								Bleed off PSI
								Rtg down -
								Rtg NOT able to pull
								TBG - planted
								✓

CEMENTING SERVICE REPORT

DS-496 PRINTED IN U.S.A.

DOWELL SCHLUMBERGER INCORPORATED

TREATMENT NUMBER 15-06-3956	DATE 2-20-92
SE	DS DISTRICT Farmington

WELL NAME AND NO. State #1	LOCATION (LEGAL) Sec 16 30S 25E	RIG NAME: B + B well Service (VORAL)
FIELD-POOL Lisbian Valley.	FORMATION Disposal well.	WELL DATA:
COUNTY/PARISH SAN JUAN.	STATE UTAH	API. NO.
NAME WEST HAZMAT	AND 7670 So. Bond Cort #200	ADDRESS Englewood, Colo
ZIP CODE 80112	SPECIAL INSTRUCTIONS Mix 1st few BBIS Light Last 5 Heavy Rig to MAINTAIN 500 PSI Backside	

IS CASING/TUBING SECURED? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	PSI	CASING WEIGHT ÷ SURFACE AREA (3.14 x R ²)
LIFT PRESSURE	PSI	PUMP PLUG TO
PRESSURE LIMIT 1500	PSI	ROTATE
RECIPROCATE	FT	No. of Centralizers

TIME	PRESSURE	VOLUME PUMPED BBL	JOB SCHEDULED FOR TIME: 1100 DATE: 2-20	ARRIVE ON LOCATION TIME: 0915 DATE: 2-20	LEFT LOCATION TIME: DATE:
0001 to 2400	TBG OR D.P.	CASING	INJECT RATE	FLUID TYPE	FLUID DENSITY
0915 - 1015					
1201	500	20	1.38	H ₂ O	8.3
1216				"	"
1220	0	520	1	H ₂ O	8.3
1222	1040	500	3.3	"	"
1224	700	490	1.8	C/G	15.8
1235	830	0	1.8	"	"
1236	630	960	0.96	H ₂ O	8.3
1254	1200	0	10 1/2	"	"
1300	1170	0	10.6	"	"
1302	1190	0	10.6	"	"
1314	1170	0	0.15	H ₂ O	8.3
1315	1170	0	10.8	"	"
1332	1130		0.15	H ₂ O	8.3
1334	1160			"	"
1340	1140				
1343					

REMARKS: 2.40 minutes working time 17.51 to 18.50 85°F
Water Chlorides 1950 - PH 7.50 MESulfates.

SYSTEM CODE	NO. OF SACKS	YIELD CU. FT/SK	COMPOSITION OF CEMENTING SYSTEMS	SLURRY MIXED BBLs	DENSITY
1.	100	1.16	C/G 17.51, 1% D127, 0.2% D46 (1160)	20.6	15.8
2.	200	1.16	C/G with 1% D127, 1% D47 side (if use pot mix to)		
3.			(188)		
4.					
5.					
6.					

BREAKDOWN FLUID TYPE	VOLUME	DENSITY	PRESSURE	MAX.	MIN.
<input type="checkbox"/> HESITATION SQ.	<input type="checkbox"/> RUNNING SQ.	CIRCULATION LOST	<input type="checkbox"/> YES <input type="checkbox"/> NO	Cement Circulated To Surf.	<input type="checkbox"/> YES <input type="checkbox"/> NO
BREAKDOWN	PSI	FINAL	PSI	DISPLACEMENT VOL.	Bbls
Washed Thru Perfs	<input type="checkbox"/> YES <input type="checkbox"/> NO	TO	FT	MEASURED DISPLACEMENT	<input type="checkbox"/> WIRELINE
PERFORATIONS	TO	TO	CUSTOMER REPRESENTATIVE	DS SUPERVISOR	
TO	2446	TO	Kent G. Stringham	H. Villanueva	

DS-496-1 PRINTED IN U.S.A.

West Hazmat

DATE _____

2-20-92

CUSTOMER WELL NAME AND NUMBER

LOCATION (LEGAL)

DS LOCATION

TREATMENT NUMBER

15-06-3051

PAGE 2

OF 2 PAGES

PAGES

Moore® 303

CEMENTING SERVICE REPORT



DS-496 PRINTED IN U.S.A.

DOWELL SCHLUMBERGER INCORPORATED

TR	MENT NUMBER	DATE
6	3037	2-21-92
STAGE	DS	DISTRICT
		Farmington

WELL NAME AND NO.		LOCATION (LEGAL)		RIG NAME:	
Slate Spiller #1		S16 T 30 R 35 E		B+B Well Service	
FIELD-POOL		FORMATION		WELL DATA:	
Leshow Valley				BOTTOM TOP	
COUNTY/PARISH		STATE		API. NO.	
San Juan		Utah			
NAME: West Hazmat					
AND					
ADDRESS					
ZIP CODE					

SPECIAL INSTRUCTIONS

Service & materials for
100 sh class & squeeze.

IS CASING/TUBING SECURED?		<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	
LIFT PRESSURE	PSI	CASING WEIGHT ÷ SURFACE AREA	(3.14 x R ²)
PRESSURE LIMIT	1800	PSI	BUMP PLUG TO
ROTATE	RPM	RECIPROCAT	FT
No. of Centralizers			

TIME	PRESSURE		VOLUME PUMPED BBL		JOB SCHEDULED FOR			ARRIVE ON LOCATION		LEFT LOCATION	
	TBG OR D.P.	CASING	INCREMENT	CUM	TIME	DATE	TIME	DATE	TIME	DATE	
0001 to 2400											
1500											
1540											
1542	0		5		1	F/W	8.3				
1547	1340	500	20.6	5	1	cml	15.8				
1600	810				1.2	cml	15.8				
1605	590				-						
1607	560		11	25.6	1	F/W	8.3				
1620	1510				-						
1631	1420				.12						
1633	1490				-						
1651	1390				.12						
1653	1470				-						

REMARKS

SYSTEM CODE	NO. OF SACKS	YIELD CU. FT/SK	COMPOSITION OF CEMENTING SYSTEMS				SLURRY MIXED	
							BBLs	DENSITY
1.	100	1.16	G, 2% SI, 1% DI27, .2% D46				20.6	15.5
2.								
3.								
4.								
5.								
6.								

BREAKDOWN FLUID TYPE		VOLUME		DENSITY		PRESSURE		MAX. 1800 MIN. 0	
<input checked="" type="checkbox"/> RESISTATION SQ.		<input type="checkbox"/> RUNNING SQ.		<input type="checkbox"/> CIRCULATION LOST		<input type="checkbox"/> YES <input type="checkbox"/> NO		Cement Circulated To Surf. <input type="checkbox"/> YES <input type="checkbox"/> NO	
BREAKDOWN		PSI	FINAL	PSI	DISPLACEMENT VOL.	Bbls		TYPE OF WELL	
Washed Thru Perfs		<input type="checkbox"/> YES <input type="checkbox"/> NO	TO	FT.	MEASURED DISPLACEMENT	<input type="checkbox"/> WIRELINE		<input type="checkbox"/> STORAGE <input type="checkbox"/> INJECTION <input type="checkbox"/> BRINE WATER <input type="checkbox"/> WILDCAT	
PERFORATIONS		TO 2446		TO	CUSTOMER REPRESENTATIVE		DS SUPERVISOR		
					Kurt Schumeller		Boyd Hoffman		



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

February 25, 1992

TO:UIC STAFF

FROM:GLENN GOODWIN, INSPECTOR *GG*

RE:CHRONOLOGY OF WORKOVER OPERATIONS ON ROONEY STATE #1 WELL
LOCATED IN SECTION 16,TOWNSHIP 30 SOUTH, RANGE 25 EAST,
SAN JUAN, COUNTY UTAH

2-13-92 Tripped in hole w/Baker cmt. retainer and set @ 7360'. Csg would not press. Dowell Services cemented w/400 sks to 2000 psi. Stung out of retainer w/18 bbls cmt. left in tubing. Attempted to cir. cmt. out. due to hole in casing could not cir. Attempted to finish pulling out of hole, tubing was cemt. in. Shut in for night.

2-14-92 Dialog on loc. went in hole backed tubing off @ 4260' Pulled tubing out. Shut in for night.

2-15-92 Tripped in hole w/Baker 7 5/8" to 4250'. Come out of hole cheking for casing leak. found hole at 2446'. Pulled packer out of hole, made up Tri-State back-off and overshot tools, went back in hole caught fish, backed tubing off @ approx. 5000'. pulled out of hole. Shut in for night.

2-16-92 went back in hole w/fishing tool, caught fish, backed tbg off another 1000'. Pulled out of hole. Shut in for night.

2-17-18-19-92 Still fishing on 19th, backed off at 6537'.

2-20-92 went in hole,set BP @ 2527',dumped 15' sand, set packer at 2379',rigged up DS and squeezed hole @ 2446' w/100 sxs. cmt.

** TRANSMIT CONFIRMATION REPORT **

Journal No. : 013
Receiver : 8017893983
Transmitter : DIV OIL GAS & MINING
Date : Mar 17,92 16:13
Document : 02 pages
Time : 01'14"
Mode : G3 NORMAL
Result : OK

* CHECK MESSAGE **

Mar 17,92 16:06

Message No.

Station Time

: Mar 17,92 15:42

LOCATION	CODE	MESSAGE
	D.O.O	Unable to Contact Remote Machine, Call Again.

789-0968



Norman H. Bangertter
Governor
Dee C. Hansen
Executive Director
Dianne R. Nielson, Ph.D.
Division Director

State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

UTAH DIVISION OF OIL, GAS AND MINING FACSIMILE TRANSMISSION COVER SHEET

DATE: 3-17-92
FAX # ~~789-3983~~ 789-0968
ATTN: Bill Ryan
COMPANY Rocky Mt. Consulting
FROM: Frank Matten
DEPARTMENT: DOGM
NUMBER OF PAGES BEING SENT (INCLUDING THIS ONE): 2

If you do not receive all of the pages, or if they are illegible, please call (801) 538-5340.

We are sending from a Murata facsimile Machine. Our telecopier number is (801) 359-3940.

MESSAGES:

Please see attached as per phone
Conservation



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

March 17, 1992

Rocky Mountain Consulting

Assume fax transmission was a plugging procedure. If assumption is correct, add plug @ base of surface casing as per R649-3-24-3.5. Put all of this information on a State of Utah Sundry Notice form and return for approval. Also, please state the fluid to be used between plugs. At the time we receive the Sundry Notice, will approve the P & A procedure, provided we concur with the procedure.

Yours truly,

F. R. Matthews
F. R. Matthews

Division of Oil, Gas and Mining
PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☒ Well File Spiller #1

☐ Suspense

☐ Other

(Location) Sec 16 Twp 30S Rng 25E

(API No.) 43037-11356

(Return Date) _____

(To - Initials) _____

1. Date of Phone Call: 3-19-92 Time: 8:00 AM

2. DOGM Employee (name) Frank Mathew (Initiated Call ☒
Talked to:

Name Bill Ryan (Initiated Call ☐ - Phone No. (801) 789-0968

of (Company/Organization) Rocky Mt. Cementing

3. Topic of Conversation: Fax of Summary received 3-18-92
for plugging of referenced well.

4. Highlights of Conversation:

Did not understand cement
system. Ken Stringham to call me back
also told him to just circ mud after
lower plug is set + cemented. Set
balanced plugs the rest of way out.
Ken Stringham called 10:50 said cement
was 25% flyash (60#/ft³) + 75%
Al G. Could tag any plugs if
necessary by adding 1% CaCl₂.
Plugging to start Monday Mar 30
1992.

Form OGC-1b

STATE OF UTAH
NATURAL RESOURCES
OIL, GAS, AND MINING

SUBMIT IN TRIPLICATE*
(Other instructions on
reverse side)

SUNDRY NOTICES AND REPORTS ON

(Do not use this form for proposals to drill or to deepen or plug back.
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR WEST HAZMAT OIL FIELD SERVICES, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 201 N. VERNAL AVE. AL, UTAH 84078 Space with any special requirements.		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location - See also space 17 below.) At surface 500' L & 500' FWL SW 1/4 SW 1/4		8. FARM OR LEASE NAME STATE
15. ELEVATIONS (Show whether OF, AT, or ABOVE) 6861'		9. WELL NO. ESPILLER #1
		10. FIELD AND POOL, OR WILDCAT LITTLE VALLEY
		11. SEC., T., R., M., OR SLK. AND SURVEY OR AREA SEC. 16, T30S, R25E
		12. COUNTY OR PARISH 13. STATE SAN JUAN UTAH

Check Appropriate Box To Indicate

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

STIMULANT FLUID ☐

REPAIRS ☐

OTHER ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETION ☐

ABANDONMENT ☒

CHANGING PLANS ☐

IN ☐

REACTURAL ☐

SHOOTING OR FLUIDIZING ☐

(Other) ☐

SEQUENT REPORT OF:

REPAIRING WELL ☐

ALTERING CASING ☐

ABANDONMENT* ☐

(Note: Report results of multiple completion on Well Completion or Completion Report and Log form.)

Remarks (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any work. Indicate subsurface locations and measured and true vertical depths for all markers and zones perti-

Est. Date 3/22/92 2 CANTIRON BRIDGE PLUG
Est. Date 3/23/92 Spot 20 Sk. Cement 6400' +/-
Spot 25 bbl. 9 lb. Mud 6022' - 6400'
Spot 70 Sk. Cement (200' in 4 1/2" & 200' in 7 5/8" 4726' - 6022'
Spot 75 bbl. 9 lb. Mud 4326' - 4727'
Spot 210 Sk. Cement 2700' - 4326'
Spot 35 bbl. 9# Mud 1800' - 2700'
Spot 25 sk. Cement 50' Above & 50' below 1050' - 1800'
Spot 35 bbl. 9# Mud 950' - 1050'
Spot 50 Sk. Cement 950' - 215'
Pump via 10 3/4" X 7 5/8" Annulus with 200Sk. Cement. 215' - 0'

System:

Allica and Cement Class G

15.4 lb./gal.

1.11 cu.ft./sk.

4.71 gal./sk.

Compressive Strength = 2300 psi in 24 hr. @ 80 F.

25:75 Poymin Cl G. Flyash 60%
S. Int. M. 1/2 1/2

I hereby certify that the foregoing is true and correct

SIGNED

OPERATIONS MANAGER

TITLE ROCKY MOUNTAIN CONSULTING DATE 3/18/92

Print name

(For State office use)

TITLE

DATE

APPROVAL IF ANY:

FAX TRANSMISSION

TO STATE OF UTAH DOGM FROM Rocky Mountain Consulting
Frank Matthews (801) 789-0968
DATE 3/18/92 PAGES TRANSMITTED 2






WELL COMPLETION WORKSHEET

Date
3/17/92KB- 6861
GL- 6847

LEASE	Well No.	Location	County	State			
ML 26505	Spiller #1	Sec 16, T30S, R 25E	SAN JUAN	UT			
WELLHEAD W.P.		ANTICIPATED SURFACE PRESSURE					
STRING	SIZE	DEPTH SET	GRADE	CPLG	WT.	BURST	
SURFACE	10 ³ / ₄	1000 KB			32.75		
PROD/INTERM	7 ⁵ / ₈	5156 KB			29.7		
LINER	4 ¹ / ₂	9507			11.6		
TUBING	2 ³ / ₈						



Note: Not To Scale.

505X Surf Plug
2005X
2405X Plug

705X plug

305X plug

6005X Total

25% Poz 75% Class 6

1% CaCl₂

Formations Tops

Top of Salt	2100
Lower Hermosa	8834
Molas	8960
Mississippian	8820
Dolomite	9240



WELL COMPLETION WORKSHEET

Date

3/1/74

AB- 6861

GL- 6891

LEASE	Well No.	Location	County	State			
ML 26505	Spiller #1	Sec 16, T30S, R 25E	SAN JUAN				
WELLHEAD W.P.		ANTICIPATED SURFACE PRESSURE					
STRING	SIZE	DEPTH SET	GRADE	CPLG	WT.	BURST	
SURFACE	10 3/4	1000 KB			32.75		
PROD/INTERM	7 5/8	5155 KB			29.7		
LINER	4 1/2	9507			11.6		
TUBING	2 3/8						

Note: Not To Scale

50 SX Surf Plug
200 SX
240 SX Plug

70 SX plug

30 SX plug

600 SX Total

1803 Top of Fish

25% Poz 75% Class 6

1% CaCl₂

7049 Bottom of fish

2300 Cmt Return

7385 Top of fish

2 3/8 Tbg (Fish)

90±'

8970 KB Packer

Formations Tops

Top of Salt 2100

Lower Hermosa 8960

Molas 8960

Mississippian 8960

Tolomite 9240

9507 T.D.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. ML 26505
2. NAME OF OPERATOR WEST HAZMAT OILFIELD SERVICES, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 201 North Vernal Ave., #1, Vernal, UT 84078		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 500' FSL & 500 FWL SW $\frac{1}{4}$, SW $\frac{1}{4}$		8. FARM OR LEASE NAME STATE
14. PERMIT NO. 43-037-11356		9. WELL NO. SPILLER #1
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6861'		10. FIELD AND POOL, OR WILDCAT
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 16, T30S, R25E
		12. COUNTY OR PARISH SAN JUAN
		13. STATE UTAH

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

☐
☐
☐
☐
☐

PULL OR ALTER CASING

☐
☐
☐
☐
☐

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANS

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

☐
☐
☐

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

☐
☐
☒
☐

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator wishes to report the subject well was plugged and abandoned on March 24, 1992. Please see the attached down hole diagram for additional details.

All production equipment has been removed and the surface recontoured.

Seeding will be conducted in the fall of 1992. The casing was cut off 2' below ground level and a steel plate set on top of the casing.

If you require additional details, please contact:

William A. Ryan
Operations Manager
ROCKY MOUNTAIN CONSULTING
350 South, 800 East
Vernal, UT 84078
(801) 789-0968

RECEIVED

MAY 26 1992

DIVISION OF
OIL GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED William A. Ryan TITLE Operations Manager DATE 5/21/92

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:



WELL COMPLETION WORKSHEET

Date

KB- Cut off @
GL- 6844'

LEASE	Well No.	Location	County				State
ML 26505	Spiller #1	Sec 16, T30S, R25E	San Juan				Utah
WELLHEAD W.P. N.A.		ANTICIPATED SURFACE PRESSURE N.A.					
STRING	SIZE	DEPTH SET	GRADE	CPLG	WT.	BURST	
SURFACE	10 3/4	1000'			32.75		
PROD/INTERM	7 5/8	5155			29.70		
LINER	4 1/2	9507			11.60		
TUBING	2 3/8						

Plug @ 200', plug set @ 1000'
50 sx cmt.

1700'

Hole in casing @ 2446, squeezed off before setting plug
2700' 250 sx cmt.

4 1/2" @ 4526 KB 200' cmt in 4 1/2 200' cmt in 7 5/8
70 sx cmt.

7 5/8 @ 5155

Cmt. top @ 5750

30 sx cmt on top @ CIBP
CIBP @ 6400

Perf. 6468-6508 & 6774-6794
Top of fish @ 6803

2 5/8 tubing fish = 90' +/-

Bottom of fish 2 7049

Retainer @ 7360
Top of fish @ 7385
Hole in casing @ 7385

End of tbg @ 8880
Packer @ 8970

Perfs from 9048-9421

T.D. 9507'

